AMENDMENT OF SOLICIT	CATION/MODIFI	CATION OF CONTRACT		CT ID CODE	PAGE OF PAGES
2. AMENDMENT/MODIFICATION NO.	3. EFFECTIVE DATE	4. REQUISITION/PURCHASE REQ. NO.		-	1 2 T NO.(If applicable)
0002	11-Aug-2003	W68MD9-3132-3333		J. FROJEC	1 NO.(11 applicable)
6. ISSUED BY CODE	DACW67	7. ADMINISTERED BY (If other than item 6)		CODE	
USA ENGINEER DISTRICT, SEATTLE ATTN: CENWS-CT P.O. BOX 3755 SEATTLE WA 98124-3755	Driewor	See Item 6			
8. NAME AND ADDRESS OF CONTRACTOR	(No., Street, County	, State and Zip Code)	X 9A. AMENE	MENT OF S	SOLICITATION NO.
				(SEE ITEM	
					ACT/ORDER NO.
			10B. DATEI	D (SEE ITE	M 13)
CODE	FACILITY COI				
X The above numbered solicitation is amended as set for		PPLIES TO AMENDMENTS OF SOLI	is extended,	X is not ex	
Offer must acknowledge receipt of this amendment p  (a) By completing Items 8 and 15, and returning  or (c) By separate letter or telegram which includes a  RECEIVED AT THE PLACE DESIGNATED FOR  REJECTION OF YOUR OFFER. If by virtue of this a  provided each telegram or letter makes reference to the	copies of the amendment reference to the solicitation of the RECEIPT OF OFFER the amendment you desire to characteristics.	ent; (b) By acknowledging receipt of this amendment and amendment numbers. FAILURE OF YOUS PRIOR TO THE HOUR AND DATE SPECIFICATION OF THE HOUR AND CONTRACTION OF THE HOUR AND CONTRACTION OF THE HOUR AND CONTRACTION OF T	ent on each copy of the ACKNOWLEDG (ED MAY RESULT) y be made by telegra	the offer submit MENT TO BE IN um or letter,	ted;
12. ACCOUNTING AND APPROPRIATION E		, 1	<u> </u>		
12 77110 1775	A A DDI JEG ONI V TO	O MODIFICATIONS OF CONTRACTS	(ODDEDG		
		O MODIFICATIONS OF CONTRACTS T/ORDER NO. AS DESCRIBED IN IT			
A. THIS CHANGE ORDER IS ISSUED PUI CONTRACT ORDER NO. IN ITEM 10A		y authority) THE CHANGES SET FOR	TH IN ITEM 14	ARE MADE	IN THE
B. THE ABOVE NUMBERED CONTRACT, office, appropriation date, etc.) SET FOI C. THIS SUPPLEMENTAL AGREEMENT	RTH IN ITEM 14, PU	RSUANT TO THE AUTHORITY OF F		(such as chan	ges in paying
D. OTHER (Specify type of modification an	d authority)				
E. IMPORTANT: Contractor is not,	is required to sign	gn this document and return	copies to the iss	uing office.	
14. DESCRIPTION OF AMENDMENT/MODII where feasible.) DACA67-03-R-0219, Hydrant Fueling Syster Phase I and II, Portland Air National guard Batter and II, Portland Air National guard Batter and State I and II, Portland Air National guard Batter and State I and II, Portland Air National guard Batter and State I and III a	n ise, Portland, Oregon document referenced in Iter	n 9A or 10A, as heretofore changed, remains unc	hanged and in full fo	orce and effect.	
15A. NAME AND TITLE OF SIGNER (Type	or print)	16A. NAME AND TITLE OF CO	ONTRACTING C	)FFICER (Ty	pe or print)
15B. CONTRACTOR/OFFEROR	15C. DATE SIGNE			1	6C. DATE SIGNED
· · · · · · · · · · · · · · · · · · ·		BY	-		
(Signature of person authorized to sign)	-	(Signature of Contracting Of	ficer)		11-Aug-2003

# SECTION SF 30 BLOCK 14 CONTINUATION PAGE

- A. This amendment two (0002) provides for the following changes:
  - (1) Revisions to Drawing Sheets 39, 40, 61, 62 and 79 by notation in the Special Clauses-00800.
- (2) Revision to Specification Section 13112, Paragraph 2.2.1; Specification Section 15060, Paragraph 2.2.6.4; and Specification Section 16415, Paragraph 2.4.
- B. The proposal submittal time and date remains August 18, 2003 at 2:00 p.m. LOCAL TIME.
- C. The attached revised sections are to be replaced in their entirety. Specifications changes are generally identified, for convenience, either by strikeout for deletions, and double underlining of text for additions or a single dark line in the right hand margin. All portions of the revised or new pages shall apply whether or not changes have been indicated.
- D. NOTICE TO OFFERORS: Offerors must acknowledge receipt of this amendment by number and date on offer. Please mark outside of envelope in which your offer is enclosed to show amendment received.

Encl:


Rev: 00800 Rev: 13112 Rev: 15060 Rev: 16415

Rev: Drawings by Notation.

# TABLE OF CONTENTS

# SPECIAL CLAUSES

PARAGRAPH NO.	PARAGRAPH TITLE
SC-1	COMMENCEMENT, PROSECUTION, AND COMPLETION OF WORK
SC-1.1	OPTION FOR INCREASED QUANTITY
SC-2	LIQUIDATED DAMAGES - CONSTRUCTION
SC-3	TIME EXTENSIONS
SC-4	<u>DELETED</u> – VARIATIONS IN ESTIMATED QUANTITIES - SUBDIVIDED ITEMS
SC-5	INSURANCE - WORK ON A GOVERNMENT INSTALLATION
SC-6	<u>DELETED</u> – CONTINUING CONTRACTS
SC-7	PERFORMANCE OF WORK BY THE CONTRACTOR
SC-8	PHYSICAL DATA
SC-9	<u>DELETED</u> – QUANTITY SURVEYS
SC-10	LAYOUT OF WORK
SC-11	RESERVED
SC-12	AIRFIELD SAFETY PRECAUTIONS
SC-13	<u>DELETED</u> – IDENTIFICATION OF GOVERNMENT-FURNISHED PROPERTY
SC-14	EQUIPMENT OWNERSHIP AND OPERATING EXPENSE SCHEDULE
SC-15	PAYMENT FOR MATERIALS DELIVERED OFF-SITE
SC-16	<u>DELETED</u> – ORDER OF PRECEDENCE
SC-17	<u>DELETED</u> – LIMITATION OF PAYMENT FOR DESIGN
SC-18	CONTRACT DRAWINGS AND SPECIFICATIONS
SC-19.	$\underline{DELETED} - TECHNICAL$ PROPOSAL - COPIES TO BE FURNISHED UPON AWARD
SC-20.	<u>DELETED</u> – COMPLIANCE CERTIFICATION
SC-21.	<u>DELETED</u> – VALUE ENGINEERING
SC-22.	EPA ENERGY STAR
SC-23	RECOVERED MATERIALS



# SPECIAL CLAUSES

# SC-1. COMMENCEMENT, PROSECUTION, AND COMPLETION OF WORK (APR 1984) (FAR 52.211-10).

The Contractor will be required to (a) commence work under this Contract within 10 calendar days after the date the Contractor receives the notice to proceed, (b) to prosecute the work diligently, and (c) to complete the entire work ready for use within 720 calendar days after notice to proceed. The time stated for completion shall include final cleanup of the premises.

# SC-1.1 OPTION FOR INCREASED QUANTITY

- a. The Government may increase the quantity of work awarded by exercising one or more of the Optional Bid Item(s) 0003 through 0006 at any time, or not at all, but no later than 240 calendar days after receipt by Contractor of notice to proceed. Notice to proceed on work Item(s) added by exercise of the option(s) will be given upon execution of consent of surety.
- b. The parties hereto further agree that any option herein shall be considered to have been exercised at the time the Government deposits written notification to the Contractor in the mails.
- c. The time allowed for completion of any optional items awarded under this contract will be the same as that for the base item(s), and will be measured from the date of receipt of the notice to proceed for the base item(s).

# SC-2. LIQUIDATED DAMAGES - CONSTRUCTION (SEP 2000) (FAR 52.211-12)

- (a) If the Contractor fails to complete the work within the time specified in the Contract, or any extension, the Contractor shall pay to the Government as liquidated damages, the sum of \$3,923.00 for each day of delay until the work is completed or accepted.
- (b) If the Government terminates the Contractor's right to proceed, the resulting damages will continue to accrue until the work is completed. These liquidated damages are in addition to excess cost of repurchase under the Termination clause of the CONTRACT CLAUSES.
- SC-3. TIME EXTENSIONS (Sept 2000) (FAR 52.211-13): Time extensions for contract changes will depend upon the extent, if any, by which the changes cause delay in the completion of the various elements of construction. The change order granting the time extension may provide that the Contract completion date will be extended only for those specific elements related to the changed work and that the remaining contract completion dates for all other portions of the work will not be altered. The change order also may provide an equitable readjustment of liquidated damages under the new completion schedule.

SC-4 DELETED.

# SC-5. INSURANCE - WORK ON A GOVERNMENT INSTALLATION (JAN 1997) (FAR 52.228-5)

- (a) The Contractor shall, at its own expense, provide and maintain during the entire performance period of this Contract at least the kinds and minimum amounts of insurance required in the Insurance Liability Schedule or elsewhere in the Contract.
- (b) Before commencing work under this Contract, the Contractor shall certify to the Contracting Officer in writing that the required insurance has been obtained. The policies evidencing required insurance shall contain an endorsement to the effect that any cancellation or any material change adversely affecting the Government's interest shall not be effective:
- (1) for such period as the laws of the State in which this Contract is to be performed prescribe; or
- (2) until 30 days after the insurer or the Contractor gives written notice to the Contracting Officer, whichever period is longer.
- (c) The Contractor shall insert the substance of this clause, including this paragraph (c), in subcontracts under this Contract that require work on a Government installation and shall require subcontractors to provide and maintain the insurance required in the Schedule or elsewhere in the Contract. The Contractor shall maintain a copy of all subcontractors' proofs of required insurance, and shall make copies available to the Contracting Officer upon request.

# SC-5.1 REQUIRED INSURANCE IN ACCORDANCE WITH FAR 28.307-2:

(1) Workers' compensation and employer's liability. Contractors are required to comply with applicable Federal and State workers' compensation and occupational disease statutes. If occupational diseases are not compensable under those statutes, they shall be covered under the employer's liability section of the insurance policy, except when Contract operations are so commingled with a Contractor's commercial operation that it would not be practical to require this coverage. Employer's liability coverage of at least \$100,000 shall be required, except in states with exclusive or monopolistic funds that do not permit workers' compensation to be written by private carriers.

# (2) General Liability.

- (a) The Contracting Officer shall require bodily injury liability insurance coverage written on the comprehensive form of policy of at least \$500,000 per occurrence.
- (b) Property damage liability insurance shall be required only in special circumstances as determined by the agency.
- (3) <u>Automobile liability</u>. The Contracting Officer shall require automobile liability insurance written on the comprehensive form of policy. The policy shall provide for bodily injury and property damage liability covering the operation of all automobiles used in connection with performing the Contract. Policies covering automobiles operated in the United States shall provide coverage of at least \$200,000 per person and \$500,000 per occurrence for bodily injury and \$20,000 per occurrence for property damage. The amount of liability coverage on other policies shall be commensurate with any legal requirements of the locality and sufficient to meet normal and customary claims.

- (4) <u>Aircraft public and passenger liability</u>. When aircraft are used in connection with performing the Contract, the Contracting Officer shall require aircraft public and passenger liability insurance. Coverage shall be at least \$200,000 per person and \$500,000 per occurrence for bodily injury, other than passenger liability, and \$200,000 per occurrence for property damage. Coverage for passenger liability bodily injury shall be at least \$200,000 multiplied by the number of seats or passengers, whichever is greater.
- (5) <u>Environmental Liability</u> If this contract includes the transport, treatment, storage, or disposal of hazardous material waste the following coverage is required.

The Contractor shall ensure the transporter and disposal facility have liability insurance if effect for claims arising out of the death or bodily injury and property damage from hazardous material/waste transport, treatment, storage and disposal, including vehicle liability and legal defense costs in the amount of \$1,000,000.00 as evidenced by a certificate of insurance for General, Automobile, and Environmental Liability Coverage. Proof of this insurance shall be provided to the Contracting Officer.

# SC-6 DELETED.

- SC-7. PERFORMANCE OF WORK BY THE CONTRACTOR (APR 1984) (FAR 52.236-1): The Contractor shall perform on the site, and with its own organization, work equivalent to at least fifteen percent (15%) of the total amount of work to be performed under the Contract. The percentage may be reduced by a supplemental agreement to this Contract if, during performing the work, the Contractor requests a reduction and the Contracting Officer determines that the reduction would be to the advantage of the Government.
- SC-8. PHYSICAL DATA (APR 1984) (FAR 52.236-4): Data and information furnished or referred to below is for the Contractor's information. The Government will not be responsible for any interpretation of or conclusion drawn from the data or information by the Contractor.
- (a) <u>Physical Conditions</u>: The indications of physical conditions on the drawings and in the specifications are the result of site investigations by test holes shown on the drawings.
- (b) <u>Weather Conditions</u>: Each bidder shall be satisfied before submitting his bid as to the hazards likely to arise from weather conditions. Complete weather records and reports may be obtained from any National Weather Service Office.
- (c) <u>Transportation Facilities</u>: Each bidder, before submitting his bid, shall make an investigation of the conditions of existing public and private roads and of clearances, restrictions, bridge load limits, and other limitations affecting transportation and ingress and egress at the jobsite. The unavailability of transportation facilities or limitations thereon shall not become a basis for claims for damages or extension of time for completion of the work.

## SC-9 DELETED.

SC-10. LAYOUT OF WORK (APR 1984) (FAR 52.236-17): The Contractor shall lay out its work from Government-established base lines and bench marks indicated on the drawings, and shall be responsible for all measurements in connection with the layout. The Contractor shall furnish, at its own expense, all stakes, templates, platforms, equipment, tools, materials, and labor required to lay out any part of the work. The Contractor shall be responsible for executing the work to the lines and grades that may be established or indicated by the Contracting Officer. The Contractor shall also be responsible for

maintaining and preserving all stakes and other marks established by the Contracting Officer until authorized to remove them. If such marks are destroyed by the Contractor or through its negligence before their removal is authorized, the Contracting Officer may replace them and deduct the expense of the replacement from any amounts due, or to become due, to the Contractor.

# SC-11. RESERVED

# SC-12. AIRFIELD SAFETY PRECAUTIONS

- (a) Definitions: As used in this clause --
  - (1) "Landing Areas" means:
- (i) the primary surfaces which are comprised of the surface of the runways, the runway shoulders, and the lateral safety zones (the length of each primary surface is the same as the runway length; the width of each primary surface is 610 meters (2,000 feet), 305 meters (1,000 feet) on each side of the runway centerline; (see footnote at end of clause)).
- (ii) the "clear zone" beyond the ends of each runway, i.e., the extension of the "primary surface" for a distance of 305 meters (1,000 feet) beyond each end of each runway;
- (iii) all taxiways plus the lateral clearance zones along each side for the length of the taxiways (the outer edge of each lateral clearance zone is laterally 76 meters (250 feet) from the far or opposite edge of the taxiway, i.e., a 23 meters (75-foot)-wide taxiway would have a combined width of taxiway and lateral clearance zones of 130 meters (425 feet); and
- (iv) all aircraft parking aprons plus the area 38 meters (125 feet) in width extending beyond each edge all around the aprons.
- (2) "Safety precaution areas" means those portions of approach-departure clearance zones and transitional zones where placement of objects incident to Contract performance might result in vertical projections at or above the approach-departure clearance surface or the transitional surface.
- (i) The "approach-departure clearance surface" is an extension of the primary surface and the clear zone at each end of each runway, for a distance of 15,240 meters (50,000 feet), first along an inclined (glide angle) and then along a horizontal plane, both flaring symmetrically about the runway centerline extended.
- (a) The inclined plane (glide angle) begins in the clear zone 61 meters (200 feet) past the end of the runway (and primary surface) at the same elevation as the end of the runway, and continues upward at a slope of 50:1 (.3048 meter (one foot) vertically for each 15.24 meters (50 feet) horizontally) to an elevation of 152 meters (500 feet) above the established airfield elevation; at that point the plane becomes horizontal, continuing at that same uniform elevation to a point 15,240 meters (50,000 feet) longitudinally from the beginning of the inclined plane (glide angle) and ending there.
- (b) The width of the surface at the beginning of the inclined plane (glide angle) is the same as the width of the clear zone; thence it flares uniformly, reaching the maximum width of 4,877 meters (16,000 feet) at the end.

- (ii) The "approach-departure clearance zone" is the ground area under the approach-departure clearance surface.
- (iii) The "transitional surface" is a sideways extension of all primary surfaces, clear zones, and approach-departure clearance surfaces along inclined planes.
  - (a) The inclined plane in each case begins at the edge of the surface.
- (b) The slope of the inclined plane is 7:1 (.3048 meter (one foot) vertically for each 2.13 meters (7 feet) horizontally), and it continues to the point of intersection with
- (1) Inner horizontal surface (which is the horizontal plane 46 meters (150 feet) above the established airfield elevation) or
- (2) Outer horizontal surface (which is the horizontal plane 152 meters (500 feet) above the established airfield elevation), whichever is applicable.
- (iv) The "transitional zone" is the ground area under the transitional surface. (It adjoins the primary surface, clear zone and approach-departure clearance zone.)

# (b) General

- (1) The Contractor shall comply with the requirements of this clause while
- (i) Operating all ground equipment (mobile or station art);
- (ii) Placing all materials; and
- (iii) Performing all work, upon and around all airfields.
- (a) The requirements of this clause are in addition to any other safety requirements of this contract.
  - (c) The Contractor shall--
    - (1) Report to the Contracting Officer before initiating any work;
    - (2) Notify the Contracting Officer of proposed changes to locations and operations;
- (3) Not permit either its equipment or personnel to use any runway for purposes other than aircraft operation without permission of the Contracting Officer, unless the runway is--
  - (i) Closed by order of the Contracting Officer, and
  - (ii) Marked as provided in paragraph (d)(2) of this clause;
- (4) Keep all paved surfaces such as runways, taxiways, and hardstands, clean at all times and, specifically, free from small stones which might damage aircraft propellers or jet aircraft;

- (5) Operate mobile equipment according to the safety provisions of this clause, while actually performing work on the airfield. At all other times, the Contractor shall remove all mobile equipment to locations--
  - (i) Approved by the Contracting Officer,
- (ii) At a distance of at least 229 meters (750 feet) from the runway centerline, plus any additional distance; and
  - (iii) Necessary to ensure compliance with the other provisions of this clause; and
- (6) Not open a trench unless material is on hand and ready for placing in the trench. As soon as practicable after material has been placed and work approved, the Contractor shall backfill and compact trenches as required by the contract. Meanwhile, all hazardous conditions shall be marked and lighted in accordance with the other provisions of this clause.
  - (e) Landing Areas

The Contractor shall--

- (1) Place nothing upon the landing areas without the authorization of the Contracting Officer.
- (2) Outline those landing areas hazardous to aircraft, using (unless otherwise authorized by the Contracting Officer) red flags by day, and electric, battery-operated low-intensity red flasher lights by night;
- (3) Obtain, at an airfield where flying is controlled, additional permission from the control tower operator every time before entering any landing area, unless the landing area is marked as hazardous in accordance with paragraph (d)(2) of this clause;
- (4) Identify all vehicles it operates in landing areas by means of a flag on a staff attached to, and flying above, the vehicle. The flag shall be .9144 meters (3 feet) square, and consist of a checkered pattern of international orange and white squares of .3048 meter (1 foot) on each side (except that the flag may vary up to 10 percent from each of these dimensions);
- (5) Mark all other equipment and materials in the landing areas, using the same marking devices as in paragraph (d)(2) of this clause; and
- (6) Perform work so as to leave that portion of the landing area which is available to aircraft free from hazards, holes, piles of material, and projecting shoulders that might damage an airplane tire.
  - (e) Safety Precaution Areas

The Contractor shall--

(1) Place nothing upon the safety precaution areas without authorization of the Contracting Officer;

- (2) Mark all equipment and materials in safety precaution areas, using (unless otherwise authorized by the Contracting Officer) red flags by day, and electric, battery-operated, low-intensity red flasher lights by night; and
- (3) Provide all objects placed in safety precaution areas with a red light or red lantern at night, if the objects project above the approach-departure clearance surface or above the transitional surface.

SC-13 DELETED.

- SC-14. EQUIPMENT OWNERSHIP AND OPERATING EXPENSE SCHEDULE (MAR 1995)-(EFARS 52.231-5000)
- (a) This clause does not apply to terminations. See 52.249-5000, Basis for Settlement of Proposals and FAR Part 49.
- (b) Allowable cost for construction and marine plant and equipment in sound workable condition owned or controlled and furnished by a contractor or subcontractor at any tier shall be based on actual cost data for each piece of equipment or groups of similar serial and series for which the Government can determine both ownership and operating costs from the contractor's accounting records. When both ownership and operating costs cannot be determined for any piece of equipment or groups of similar serial or series equipment from the contractor's accounting records, costs for that equipment shall be based upon the applicable provisions of EP 1110-1-8, Construction Equipment Ownership and Operating Expense Schedule, Region VIII. Working conditions shall be considered to be average for determining equipment rates using the schedule unless specified otherwise by the contracting officer. For equipment not included in the schedule, rates for comparable pieces of equipment may be used or a rate may be developed using the formula provided in the schedule. For forward pricing, the schedule in effect at the time of negotiations shall apply. For retroactive pricing, the schedule in effect at the time the work was performed shall apply.
- (c) Equipment rental costs are allowable, subject to the provisions of FAR 31.105(d)(ii) and FAR 31.205-36. Rates for equipment rented from an organization under common control, lease-purchase arrangements, and sale-leaseback arrangements, will be determined using the schedule, except that actual rates will be used for equipment leased from an organization under common control that has an established practice of leasing the same or similar equipment to unaffiliated lessees.
- (d) When actual equipment costs are proposed and the total amount of the pricing action exceeds the small purchase threshold, the contracting officer shall request the contractor to submit either certified cost or pricing data, or partial/limited data, as appropriate. The data shall be submitted on Standard Form 1411, Contract Pricing Proposal Cover Sheet.
- (e) Copies of EP1110-1-8 "Construction Equipment Ownership and Operating Expense Schedule" Volumes 1 through 12 are available in Portable Document Format (PDF) and can be viewed or downloaded at http://www.usace.army.mil/inet/usace-docs/eng-pamplets/cecw.htm. A CD-ROM containing (Volumes 1-12) is available through either the Superintendent of Documents or Government bookstores. For additional information telephone 202-512-2250, or access on the Internet at http://www.access.gpo.gov/su\_docs.

# SC-15. PAYMENT FOR MATERIALS DELIVERED OFF-SITE (MAR 1995)-(EFARS 52.232-5000)

- (a) Pursuant to FAR clause 52.232-5, Payments Under Fixed Priced Construction Contracts, materials delivered to the contractor at locations other than the site of the work may be taken into consideration in making payments if included in payment estimates and if all the conditions of the General Provisions are fulfilled. Payment for items delivered to locations other than the work site will be limited to:

  (1) materials required by the technical provisions; or (2) materials that have been fabricated to the point where they are identifiable to an item of work required under this contract.
- (b) Such payment will be made only after receipt of paid or receipted invoices or invoices with canceled check showing title to the items in the prime contractor and including the value of material and labor incorporated into the item. In addition to petroleum products, payment for materials delivered offsite is limited to the following items: Any other construction material stored offsite may be considered in determining the amount of a progress payment.

SC-16 AND SC-17 DELETED.

- SC-18. CONTRACT DRAWINGS AND SPECIFICATIONS (AUG 2000)(DOD FAR SUPP 252.236-7001)
- (a) The Government will provide to the Contractor, without charge, one set of contract drawings and specifications, except publications incorporated into the technical provisions by reference, in electronic or paper media as chosen by the Contracting Officer.
  - (b) The Contractor shall--
    - (1) Check all drawings furnished immediately upon receipt;
    - (2) Compare all drawings and verify the figures before laying out the work;
    - (3) Promptly notify the Contracting Officer of any discrepancies;
    - (4) Be responsible for any errors which might have been avoided by complying with this paragraph (b); and
    - (5) Reproduce and print contract drawings and specifications as needed.
  - (c) In general—
    - (1) Large scale drawings shall govern small scale drawings; and
    - (2) The Contractor shall follow figures marked on drawings in preference to scale measurements.
- (d) Omissions from the drawings or specifications or the misdescription of details of work which are manifestly necessary to carry out the intent of the drawings and specifications, or that are customarily performed, shall not relieve the Contractor from performing such omitted or misdescribed details of the work. The Contractor shall perform such details as if fully and correctly set forth and described in the drawings and specifications.

(e) The work shall conform to the specifications and the contract drawings identified in the index of drawings attached at the end of the Special Clauses.

# SC-19 THROUGH SC-21 DELETED.

- SC-22. EPA ENERGY STAR: The Government requires that certain equipment be Energy Star compliant. Initially, the sole Energy Star requirement shall be the self certification by the bidder that the specified equipment is Energy Star compliant. Within 3 months of the availability of an EPA sanctioned test for Energy Star compliance, the Contractor shall submit all equipment upgrades and additions for testing and provide proof of compliance to the Government upon completion of testing. Testing shall be at the Contractor's expense.
- SC-23. <u>RECOVERED MATERIALS</u>: The Corps of Engineers encourages all bidders to utilize recovered materials to the maximum extent practicable. The attached APPENDIX R contains procurement guidelines for products containing recovered materials.

# APPENDIX R

# PART 247 - COMPREHENSIVE PROCUREMENT GUIDELINE FOR PRODUCTS CONTAINING RECOVERED MATERIALS

40 CFR Ch. 1 (9-1-99 Edition)

**Subpart B-Item Designations** 

§ 247.10 Paper and paper products.

Paper and paper products, excluding building and construction paper grades.

# § 247.11 Vehicular products.

- (a) Lubricating oils containing re-refined oil, including engine lubricating oils, hydraulic fluids, and gear oils, excluding marine and aviation oils.
- (b) Tires, excluding airplane tire
- (e) Reclaimed engine coolants, excluding coolants used in non-vehicular applications.

# 247.12 Construction products.

- (a) Building insulation product including the following items:
- (1) Loose-fill insulation, including but not limited to cellulose fiber, mineral fibers (fiberglass and rock vermiculite, and perlite;
- (2) Blanket and batt insulation, including but not limited to mineral fibers (fiberglass and rock wool).
- (3) Board (sheathing, roof decking wall panel) insulation, including but not limited to structural fiberboard and laminated paperboard products perlite composite board, polyurethane, polyisocyanurate, polystyrene, phenolics, and composites; and
- (4) Spray-in-place insulation, including but not limited to foam-in-place polyurethane and polyisocyanurate and spray-on cellulose.
- (b) Structural fiberboard and laminated paperboard products for applications other than building insulation, including building board, sheathing shingle backer, sound deadening board, roof insulating board, insulating wallboard, acoustical and non-acoustical ceiling tile, acoustical and non-acoustical lay-in panels, floor underlayments, and roof overlay (cover board).
- (c) Cement and concrete, including concrete products such as pipe and block, containing coal fly as ground granulated blast furnace (GGBF) slag.
- (d) Carpet made of polyester fiber use in low- and medium-wear applications.
- (e) Floor tiles and patio block containing recovered rubber or plastic.
- (f) Shower and restroom dividers/partitions containing recovered plastic or steel.
- (g) (1) Consolidated latex paint used for covering graffiti; and
- (2) Reprocessed latex paint used for interior and exterior architectural applications such as wallboard, ceilings, and trim; gutter boards; and concrete, stucco, masonry, wood and metal surfaces.

# §247.13 Transportation products.

- (a) Traffic barricades and traffic cones used in controlling or restricting vehicular traffic.
- (b) Parking stops made from concrete or containing recovered plastic or rubber.
- (c) Channelizers containing recovered plastic or rubber.
- (d) Delineators containing recovered plastic, rubber, or steel.

(e) Flexible delineators containing recovered plastic.

# § 247.14 Park and recreation products

- (a) Playground surfaces and running tracks containing recovered rubber or plastic.
- (b) Plastic fencing containing recovered plastic for use in controlling snow or sand drifting and as a warning/safety barrier in construction or other applications.

# 247.15 Landscaping products.

- (a) Hydraulic mulch products containing recovered paper or recovered wood used for hydroseeding and as an over-spray for straw mulch in landscaping, erosion control, and soil reclamation.
- (b) Compost made from yard trimmings, leaves, and/or grass clippings for use in landscaping, seeding of grass or other plants on roadsides and embankments, as a nutritious mulch under trees and shrubs, and in erosion control and soil reclamation.
  - (c) Garden and soaker hoses containing recovered plastic or rubber.
- (d) Lawn and garden edging containing recovered plastic or rubber.

# § 247.16 Non-paper office product.

- (a) Office recycling containers and office waste receptacles.
- (b) Plastic desktop accessories.
- (c) Toner cartridges.
- (d) Binders.
- (e) Plastic trash bags.
- (f) Printer ribbons.
- (g) Plastic envelopes.

## § 247.17 Miscellaneous products.

Pallets containing recovered wood, plastic, or paperboard.

# INDEX OF DRAWINGS

# Hydrant Fueling System, Phases I & II Portland Air National Guard Base, Portland, OR TQKD 012251A, TQKD 012251B Drawing No. 312s/121-10-01

SHEET NUMBER	PLATE NUMBER	TITLE	REVISION NUMBER	DATE
1	D1.01	Title Sheet		16 JUN 03
2	D2.01	Index of Drawings		16 JUN 03
3	D3.01	Civil, Architectural and Mechanical Legend		16 JUN 03
4	D4.01	Electrical Legend Symbols		16 JUN 03
5	D4.02	Electrical Legend Symbols		16 JUN 03
6	D5.01	Abbreviations		16 JUN 03
		Fuel Storage Area (A Series Drawings)		
7	AP1.01	Location Plan and Vicinity Map		16 JUN 03
8	AP1.02	Composite Site Plan		16 JUN 03
9	AP1.03E	Construction Phasing Plan – Phase I		16 JUN 03
10	AP1.03W	Construction Phasing Plan – Phase II		16 JUN 03
11	AP1.04	Construction Phasing Notes And Details		16 JUN 03
12	AP1.05	POL Area Phasing Plan		16 JUN 03
13	AP1.06	Pumphouse Phasing Plan 1 Of 2		16 JUN 03
14	AP1.07	Pumphouse Phasing Plan 2 Of 2		16 JUN 03
15	AP2.01	Removal Plan – Fuel Storage Area		16 JUN 03
16	AP2.02	Removal Plan – Hydrant Loop Route		16 JUN 03
17	AP3.01	Site Plan – Fuel Storage Area		16 JUN 03
18	AP3.02	Site Plan – Hydrant Loop Route		16 JUN 03
19	AP4.01	Site and Fence Details		16 JUN 03
20	AC1.01	Grading and Drainage Plan – Fuel Storage		16 JUN 03

SHEET NUMBER	PLATE NUMBER	TITLE	REVISION NUMBER	DATE
		Area		
21	AC1.02	Grading And Drainage Plan – Hydrant Loop Route		16 JUN 03
22	A2.01	Grading Sections – OPS Building and Pump House		16 JUN 03
23	AC8.01	Storm Line Profile & Details – Phase 1		16 JUN 03
24	AS8.01	Structural Details		16 JUN 03
25	AS8.02	Structural Details		16 JUN 03
26	AM0.01	POL Area Flow Diagram		16 JUN 03
27	AMR.01	POL Area Site Plan – Demolition		16 JUN 03
28	AM1.01	POL Site Plans – New Work		16 JUN 03
29	AM3.01	Fuel Piping Profiles		16 JUN 03
30	AM4.01	Enlarged Plan – Fill Stands And HHT Check Out		16 JUN 03
31	AM5.01	Mechanical Fueling Details		16 JUN 03
32	AEU.01	Electrical Site Plan – Fuel Storage Area		16 JUN 03
33	AEU.02	Electrical Site Plan – Control Route		16 JUN 03
34	AEC.01	Cathodic Protection Plan Fuel Storage Area		16 JUN 03
35	AEC.02	Cathodic Protection Plan Hydrant Loop Route		16 JUN 03
36	AED.01	Details		16 JUN 03
37	AED.02	Details		16 JUN 03
38	AED.03	Cathodic Protection Details		16 JUN 03
		Apron (B Series Drawings)		
39	B1A1.01	Removal Plan – Base Bid & Bid Options – Phase I – East Apron		16 JUN 03

SHEET NUMBER	PLATE NUMBER	TITLE	REVISION NUMBER	DATE
40	B2Q1.02	Removal Plan – Bid Options – Phase II West Apron		16 JUN 03
41	B1Q2.01	Pavement Removal Sections – Phase I – East Apron		16 JUN 03
42	B2A2.02	Pavement Removal Sections – Phase II – West Apron		16 JUN 03
43	B1A3.01	Site Plan – Base Bid – Phase I – East Apron		16 JUN 03
44	B1Q3.02	Site Plan – Bid Options 2 & 3 – Phase I – East Apron		16 JUN 03
45	B2Q3.03	Site Plan – Bid Option 1 – Phase II – West Apron		16 JUN 03
46	B2Q3.04	Site Plan – Bid Options 2 & 3 – Phase II – West Apron		16 JUN 03
47	B1Q4.01	Grading And Drainage Plan – Base Bid – Phase I – East Apron		16 JUN 03
48	B1Q4.02	Grading And Drainage Plan – Bid Options 2 & 3 – Phase I – East Apron		16 JUN 03
49	B2Q4.03	Grading And Drainage Plan – Bid Option 1 – Phase II – West Apron		16 JUN 03
50	B2Q4.04	Grading And Drainage Plan – Bid Options 2 & 3 – Phase II – West Apron		16 JUN 03
51	B1Q7.01	Slotted Drain Details – Phase I – East Apron		16 JUN 03
52	B2Q7.02	Slotted Drain Details – Phase II – West Apron		16 JUN 03
53	B1QA.01	Joint Layout – Base Bid – Phase I – East Apron		16 JUN 03
54	B1QA.02	Joint Layout – Bid Options 2 & 3 – Phase I – East Apron		16 JUN 03
55	B2QA.03	Joint Layout – Bid Option 1 – Phase II – West Apron		16 JUN 03
56	B2QA.04	Joint Layout – Bid Options 2 & 3 – Phase II – West Apron		16 JUN 03

SHEET NUMBER	PLATE NUMBER	TITLE	REVISION NUMBER	DATE
57	B1QB.01	Pavement Sections – Base Bid – Phase I – East Apron		16 JUN 03
58	B1QB.02	Pavement Sections – Bid Options 2 & 3 – Phase I – East Apron		16 JUN 03
59	B2QB.03	Pavement Sections – Bid Option I – Phase II – West Apron		16 JUN 03
60	B2QB.04	Pavement Sections – Bid Options 2 & 3 – Phase II – West Apron		16 JUN 03
61	B1QC.01	Joint And Miscellaneous Details – Phase I – East Apron		16 JUN 03
62	B2QC.02	Joint And Miscellaneous Details – Phase II – West Apron		16 JUN 03
63	B1QD.01	Enlarged Partial Plan Proposed Pavement Grades – Base Bid – Phase I – East Apron		16 JUN 03
64	B1QD.02	Enlarged Partial Plan Proposed Pavement Grades – Base Bid – Phase I – East Apron		16 JUN 03
65	B1QD.03	Enlarged Partial Plan Proposed Pavement Grades – Bid Options 2 & 3 – Phase I – East Apron		16 JUN 03
66	B1QD.04	Enlarged Partial Plan Proposed Pavement Grades – Bid Options 2 & 3 – Phase I – East Apron		16 JUN 03
67	B1QD.05	Enlarged Partial Plan Proposed Pavement Grades – Bid Options 2 & 3 – Phase I – East Apron		16 JUN 03
68	B1QD.06	Enlarged Partial Plan Proposed Pavement Grades – Bid Option 1 – West Apron		16 JUN 03
69	B1QD.07	Enlarged Partial Plan Proposed Pavement Grades – Bid Option 1 – West Apron		16 JUN 03
70	B1QD.08	Enlarged Partial Plan Proposed Pavement Grades – Bid Options 2 & 3 – Phase II – West Apron		16 JUN 03

SHEET NUMBER	PLATE NUMBER	TITLE	REVISION NUMBER	DATE
71	B1QD.09	Enlarged Partial Plan Proposed Pavement Grades – Bid Options 2 & 3 – Phase II – West Apron		16 JUN 03
72	B1QD.10	Enlarged Partial Plan Proposed Pavement Grades – Bid Options 2 & 3 – Phase II – West Apron		16 JUN 03
73	B1G2.01	Boring Logs – Phase I – East Apron		16 JUN 03
74	B2G2.02	Boring Logs – Bid Option 1 - Phase II – West Apron		16 JUN 03
75	B158.01	Structural Details		16 JUN 03
76	B158.02	Structural Details		16 JUN 03
77	B1M0.01	Hydrant Loop Flow Diagram		16 JUN 03
78	B1M1.01	Mechanical Site Plan – Phase I		16 JUN 03
79	B1M3.01	Fuel Pipe Profiles		16 JUN 03
80	B1M5.01	Hydrant Outlet Pit Detail		16 JUN 03
81	B1M5.02	Isolation Valve Pit & Fueling Details		16 JUN 03
82	B2M1.01	Mechanical Site Plan – Phase II		16 JUN 03
83	B1EU.01	Electrical Site Plan – Base Bid – Phase I – East Apron		16 JUN 03
84	B2EU.02	Electrical Site Plan – Bid Option 1 – Phase II – West Apron		16 JUN 03
85	B1EC.01	Cathodic Protection Site Plan, Base Bid – Phase I – East Apron		16 JUN 03
86	B2EC.02	Cathodic Protection Site Plan, Bid Option 1 – Phase II – West Apron		16 JUN 03
87	BED.01	Details – Grounding and EFSO		16 JUN 03
88	BED.02	Details		16 JUN 03

SHEET NUMBER	PLATE NUMBER	TITLE	REVISION NUMBER DATE	
		Pumphouse (C Series Drawings)		
89	CA1.01	Pumphouse – Floor, Roof And Reflected Ceiling Plans	16 JUN 03	
90	CA4.01	Pumphouse – Elevations	16 JUN 03	
91	CS1.01	Structural Notes And Abbreviations	16 JUN 03	
92	CS2.01	Pumphouse – Structural Plan	16 JUN 03	
93	CS2.02	Pumphouse – Pipe Support Plan	16 JUN 03	
94	CS5.01	Pumphouse – Structural Sections	16 JUN 03	
95	CS8.01	Pumphouse – Structural Details	16 JUN 03	
96	CM0.01	Pumphouse – System Flow Diagram	16 JUN 03	
97	CM0.02	Pumphouse – Sequence Of Operations	16 JUN 03	
98	CMR.01	Pumphouse – Mechanical Demolition	16 JUN 03	
99	CM1.01	Pumphouse – Mechanical New Work	16 JUN 03	
100	CM3.01	Pumphouse – Sections	16 JUN 03	
101	CM3.02	Pumphouse – Sections	16 JUN 03	
102	CM5.01	Pumphouse – Mechanical Fueling Details	16 JUN 03	
103	CER.01	Pumphouse – Electrical Removal Plan	16 JUN 03	
104	CE1.01	Pumphouse – Lighting Plan	16 JUN 03	
105	CE2.01	Pumphouse – Power & Systems Plans	16 JUN 03	
106	CE4.01	Pumphouse – Grounding & Lightning Protection Plans	16 JUN 03	
107	CE7.01	Pumphouse – Electrical Details	16 JUN 03	
		Control Building (D Series Drawings)		
108	DA1.01	Control Building – Floor And Roof Plan	16 JUN 03	
109	DA4.01	Control Building – Elevations And Section	16 JUN 03	
110	DS2.01	Control Building – Structural Plan	16 JUN 03	

SHEET NUMBER	PLATE NUMBER	TITLE	REVISION NUMBER	DATE
111	DS5.01	Control Building – Structural Sections		16 JUN 03
112	DS8.01	Control Building – Structural Details		16 JUN 03
113	DER.01	Control Building – Electrical Removal Plan		16 JUN 03
114	DE1.01	Control Building – Lighting Plan		16 JUN 03
115	DE2.01	Control Building – Power Plan		16 JUN 03
116	DE4.01	Control Building – Grounding & Lightning Protection Plans		16 JUN 03
117	DE5.01	Control Building – One-Line Removal Diagram		16 JUN 03
118	DE5.02	Control Building – One-Line Diagram		16 JUN 03
119	DE6.01	Control Building – Motor Control Center Schedule & Details		16 JUN 03
120	DE6.02	Control Building – Conduit & Conductor Schedule		16 JUN 03
121	DE7.01	Control Building – Pump Control Panel Elevation & Details		16 JUN 03
122	DE7.02	Control Building – Graphic Display Detail		16 JUN 03
123	DE8.01	Control Building – PCP Control System Block Diagram		16 JUN 03
124	DE8.02	Control Building – Control System 1/O Sheet 1		16 JUN 03
125	DE8.03	Control Building – Control System I/O – Sheet 2		16 JUN 03
126	DE8.04	Control Building – Control System I/O – Sheet 3		16 JUN 03
127	DE8.05	Control Building – Terminal Block Connections – Field Devices		16 JUN 03
128	DE8.06	Control Building – Control Diagrams		16 JUN 03
129	DE8.07	Control Building – Control Diagrams		16 JUN 03

SHEET NUMBER	PLATE NUMBER	TITLE	REVISION NUMBER	DATE
		OPS Building (E Series Drawings)		
130	EA1.01	OPS Building – Demolition Plan		16 JUN 03
131	EA1.02	OPS Building – Floor And Reflected Ceiling Plan Addition		16 JUN 03
132	EA3.01	OPS Building – Roof Demolition And Addition Plan		16 JUN 03
133	EA4.01	OPS Building – Elevations		16 JUN 03
134	EA5.01	OPS Building – Wall Demolition And Addition Section		16 JUN 03
135	EA6.01	OPS Building – Door Schedule, Room Finish Schedule, Details, And Elevations		16 JUN 03
136	ES2.01	OPS Building – Structural Plan		16 JUN 03
137	ES2.02	OPS Building – Roof Demo Plan		16 JUN 03
138	ES5.01	OPS Building – Structural Sections		16 JUN 03
1339	EM1.01	OPS Building – Mechanical Demolition & New Work		16 JUN 03
140	EER.01	OPS Building – Electrical Removal Plan		16 JUN 03
141	EE1.01	OPS Building – Lighting Plan		16 JUN 03
142	EE2.01	OPS Building – Power And Systems Plans		16 JUN 03
143	EE3.01	OPS Building – Fire Alarm Plan		16 JUN 03
144	EE7.01	OPS Building – Details – RCC Panel		16 JUN 03

# **REVISIONS TO DRAWINGS BY NOTATION**

Drawing Sheets 39 and 40: To Note 3, add additional text: "Over every existing panel where a crack is repaired, the subsequent PCC overlay panel shall be reinforced with welded wire fabric, WWF 6 x 6 - W2.0 x W2.0, as indicated on the PCC overlay details. Assume 30 reinforced panels for basis of bid."

Drawing Sheets 61 and 62: In Details 6 and 7, show the width of the expansion joints to be <sup>3</sup>/<sub>4</sub>".

Drawing, Sheet 79: Change "Station 33+6.75" to "Station 33+9.75."

# STANDARD DETAILS BOUND IN THE SPECIFICATIONS

DRAWING NUMBER	SHEET NUMBER	TITLE	DATE
SECTION 0150	01 - CONSTRUC	TION FACILITIES AND TEMPORARY CON	VTROLS
	1 & 2	U.S. Air Force Project Construction Sign	84JUN20
	1	Hard Hat Sign	10SEP90

END OF SECTION

## SECTION 13112

## CATHODIC PROTECTION SYSTEM (IMPRESSED CURRENT)

## PART 1 GENERAL

## 1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

# AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 53/A 53M (2001) Pipe, Steel, Black and Hot-Dipped, Zinc-Coated Welded and Seamless

ASTM D 1248 (1998) Polyethylene Plastics Molding and Extrusion Materials

## NACE INTERNATIONAL (NACE)

NACE RP0169 (1996) Control of External Corrosion on Underground or Submerged Metallic Piping

Onderground of Submerged Metallic Pipi

Systems

NACE RP0572 (1995) Design, Installation, Operation,

and Maintenance of Impressed Current Deep

Groundbeds

# NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA TC 2 (1998) Electrical Polyvinyl Chloride (PVC)

Tubing (EPT) and Conduit (EPC-40 and

EPC-80)

NEMA WC 5 (1992; Rev 2 1996) Thermoplastic-Insulated

Wire and Cable for the Transmission and

Distribution of Electrical Energy

## NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70 (2002) National Electrical Code

# UNDERWRITERS LABORATORIES (UL)

UL 467 (1993; Rev thru Apr 1999) Grounding and

Bonding Equipment

UL 506 (1994; R Oct 1997) Specialty Transformers

UL 510 (1994; Rev thru Apr 1998) Polyvinyl

Chloride, Polyethylene, and Rubber

Insulating Tape

UL 514A

(1996; Rev Dec 1999) Metallic Outlet Boxes

## 1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Drawings; G-AE

SD-03 Product Data

Miscellaneous Materials; G-AE

Equipment; G-AE

Spare Parts

SD-06 Test Reports

Tests and Measurements; G-AO

Test reports in booklet form tabulating field tests and measurements performed, upon completion and testing of the installed system and icasing and interference tests, final system test verifying protection, insulated joint and bond tests, . Each test report shall indicate the final position of controls. A certified test report showing that the connecting method has passed a 120-day laboratory test without failure at the place of connection, wherein the anode is subjected to maximum recommended current output while immersed in a 3 percent sodium chloride solution.

SD-07 Certificates

Cathodic Protection System

Proof that the materials and equipment furnished under this section conform to the specified requirements contained in the referenced standards or publications. The label or listing by the specified agency will be acceptable evidence of such compliance.

Services of "Corrosion Expert"

Evidence of qualifications of the "corrosion expert".

- (a) The "corrosion expert's" name and qualifications shall be certified in writing to the Contracting Officer prior to the start of construction.
- (b) Certification shall be submitted giving the name of the firm, the number of years of experience, and a list of not less than five (5) of the firm's installations three (3) or more years old that have been tested and found satisfactory.

# SD-10 Operation and Maintenance Data

# Cathodic Protection System

Six copies of operating manual outlining the step-by-step procedures required for system startup, operation, adjustment of current flow, and shutdown. The manuals shall include the manufacturer's name, model number, service manual, parts list, and brief description of all equipment and their basic operating features. Six copies of maintenance manual listing routine maintenance procedures, recommendation for maintenance testing, possible breakdowns and repairs, and troubleshooting guides. The manuals shall include single line diagrams for the system as installed; instructions in making pipe- to-reference cell potential measurements and frequency of monitoring; instructions for dielectric connections, interference and sacrificial anode bonds; instructions shall include precautions to ensure safe conditions during repair of pipe system.

# Training Course

The proposed Training Course Curriculum (including topics and dates of discussion) indicating that all of the items contained in the operating and maintenance instructions, as well as demonstrations of routine maintenance operations, including testing procedures included in the maintenance instructions, are to be covered.

# 1.3 GENERAL REQUIREMENTS

A complete, operating impressed current cathodic protection system in accordance with NFPA 70, the applicable federal, state and local regulations, and the requirements of this contract shall be provided. addition to the minimum requirements of these specifications, . The system shall include planning, inspecting the installation, adjusting and testing cathodic protection and test system using rectifiers and impressed current anodes, supplemented with sacrificial anodes as needed, for utilities and equipment shown. The cathodic protection system shall also include cables, connectors, splices, corrosion protection test stations, ace power panels, and any other equipment required for a complete operating system providing the specified protection. The cathodic protection system shall include (a) calculations for rectifier, anodes, and any recommendations for  $\frac{1}{2}$ supplementing or changing the minimum design criteria to provide the specified potentials and (b) equipment, wiring, and wiring devices necessary to produce a continuous flow of direct current from anodes in the soil electrolyte to the pipe surfaces. The installation shall meet the specified protection criteria for a 25 year life.

## 1.3.1 Contractor's Modifications

The specified system is based on an impressed current system . The Contractor may modify the cathodic protection system after review of the project, site verification and analysis if the proposed modifications include the impressed current anodes and rectifiers and will provide better overall system performance. The modifications shall be fully described, shall be approved by the Contracting Officer and shall meet the following criteria. The proposed system shall achieve a minimum pipe-to-soil "Instant Off" potential of minus 850 millivolts with reference to a saturated copper-copper sulfate reference cell on the underground metallic

components of the piping. The Contractor shall take resistivity measurements of the soil in the vicinity of the pipes and ground bed sites; based upon the measurements taken, the current and voltage of the rectifier shall be adjusted as required to produce a minimum of minus 850 millivolts "Instant Off" potential between the structure being tested and the reference cell. This potential shall be obtained over 95 percent of the metallic area without the "Instant Off" potential exceeding 1200 millivolts.

#### 1.3.2 Isolators

Isolators are required to isolate the indicated pipes from any other structure. Isolators shall be provided with lightning protection and a test station as shown.

## 1.3.3 Anodes and Bond Wires

Anodes shall be installed in sufficient number and of the required type, size and spacing to obtain a uniform current distribution of 2.5 milliamperes per square foot minimum to underground metal surfaces. For each cathodic protection system, the metallic components and structures to be protected shall be made electrically continuous. This shall be accomplished by installing bond wires between the various structures. Bonding of existing buried structures may also be required to preclude detrimental stray current effects and safety hazards. Provisions shall be included to return stray current to its source without damaging structures intercepting the stray current. The electrical isolation of underground facilities in accordance with acceptable industry practice shall be included under this section.

# 1.3.3 Services of "Corrosion Expert"

The Contractor shall obtain the services of a "corrosion expert" to supervise, inspect, and test the installation and performance of the cathodic protection system. "Corrosion expert" refers to a person, who, by reason of thorough knowledge of the physical sciences and the principles of engineering and mathematics, acquired by professional education and related practical experience, is qualified to engage in the practice of corrosion control of buried metallic piping and tank systems. Such a person must be accredited or certified by the National Association of Corrosion Engineers (NACE) as a NACE Accredited Corrosion Specialist or a NACE certified Cathodic Protection (CP) Specialist or be a registered professional engineer who has certification or licensing that includes education and experience in corrosion control of buried or submerged metallic piping and tank systems, if such certification or licensing includes 5 years experience in corrosion control on underground metallic surfaces of the type under this contract. The "corrosion expert" shall supervise installation and testing of all cathodic protection.

## 1.4 DRAWINGS

Six copies of detail drawings consisting of a complete list of equipment and material including manufacturer's descriptive and technical literature, catalog cuts, results of system design calculations including soil resistivity, installation instructions and certified test data stating the maximum recommended anode current output density and the rate of gaseous production, if any, at that current density. Detail drawings shall contain complete wiring and schematic diagrams and any other details required to demonstrate that the system has been coordinated and will function properly as a unit.

# 1.5 EQUIPMENT

Within 30 days after receipt of notice to proceed, an itemized list of equipment and materials including item number, quantity, and manufacturer of each item. The list shall be accompanied by a description of procedures for each type of testing and adjustment, including testing of coating for thickness and holidays. Installation of materials and equipment shall not commence until this submittal is approved.

#### 1.6 SPARE PARTS

Spare parts data for each different item of material and equipment specified, after approval of detail drawings and not later than 2 months prior to the date of beneficial occupancy. The data shall include a complete list of parts, special tools, and supplies, with current unit prices and source of supply. One spare anode of each type shall be furnished.

#### PART 2 PRODUCTS

## 2.1 IMPRESSED CURRENT ANODES

## 2.1.1 Bare High Silicon Cast-Iron Anodes

Cast-iron anodes shall be of the size indicated and shall conform to the following requirements:

## 2.1.1.1 Chemical Composition (Nominal)

Element	Percent by Weight Grade 2
Silicon	14.20-14.75
Manganese	1.50 Max.
Carbon	0.75-1.15
Chromium	3.25-5.00
Iron	Balance

# 2.1.1.2 Electrical Resistivity

Seventy-two microhm-centimeter at 20 degrees F.

# 2.1.1.3 Physical Properties (Nominal)

Tensile strength	15,000 psi
Compressive strength	100,000 psi
Brinell hardness	520
Density	7.0 grams per cubic centimeter
Melting point	2300 degrees F
Coefficient of	0.00000733 centimeter
expansion from 32	per degree F
to 212 degrees F	

# 2.1.2 Canister Contained Anodes

Canister contained anodes shall be packed at the factory in sheet metal canisters with calcined petroleum coke breeze. The coke shall have a resistivity of  $0.1\ ohm-cm$  tested at  $150\ psi$ . The coke shall be  $70\ ohm-cm$ 

lbs/cubic foot or greater. The maximum particle size shall be 0.039 inches and the coke shall be dust-free. The canisters shall be capped with tight fitting end caps secured to the body of the canister. The canister shall provide a minimum annular space of 3 inches all around the anode. The connecting cable shall pass through a hole in an end cap designed to be tight fitting with the cable and protected from sharp edges with a plastic or rubber grommet. The anodes shall be centered in the canisters and the annular space filled with coke breeze compacted in place.

# 2.1.3 Anode Connecting Cables

Anodes shall have connecting cables installed at the factory.

## 2.1.4 Mixed Metal Oxide Anodes

Mixed metal oxide anodes shall be of the size indicated and shall conform to the following requirements.

# 2.1.4.1 Conductive Material

The electrically conductive coating shall contain a mixture consisting primarily of iridium, tantalum, and titanium oxides. The average composition is generally a 50/50 atomic percent mixture of iridium and titanium oxides, with a small amount of tantalum. The resistivity, as tested by the manufacturer, shall be no more than 0.002 ohm-centimeter, and the bond strength shall be greater than 7.25 ksi to guarantee the current capacity life and the quality of the conductive ceramic coating. The adhesion or bond strength shall be determined by epoxy bonding a 0.1 inch diameter stud to the ceramic coating and measuring the load to failure (about 10.15 ksi) of either the epoxy or the interface between the coating and the substrate. The anode must be inert and the electrically conductive ceramic coating dimensionally stable. The ceramic coated anode shall be capable of sustaining a current density of 100 ampere per 10.764 square feet in an oxygen generating electrolyte at 150 degrees F for 20 years, to ensure the current capacity life. An accelerated current capacity life test shall be performed by the manufacturer on every lot of anode wire used to construct the anode as described. The mixed metal oxide coating shall be applied to the wire anode by a firm that is regularly engaged in and has a minimum 5 years experience in manufacturing and applying mixed metal oxide coatings to titanium anode substrates. The mixed metal oxide must be sintered to the titanium surface as to remain tightly bound to the surface when bent 180 degrees onto itself.

# 2.1.4.2 Anode Life Test

The anode wire material shall sustain current densities of 100 ampere per 10.764 square feet in an oxygen generating electrolyte for 20 years. The manufacturer shall certify that a representative sample taken from the same lot used to construct the anode, has been tested and meets the following criteria. The test cell sustains a current density of 10,000 ampere per 10.764 square feet in a 15 weight percent sulfuric acid electrolyte at 150 degrees F without an increase in anode to cathode potential of more than 1 volt. The cell containing the anode shall be powered with a constant current power supply for the 30 day test period. The representative sample shall be 5 inch in length taken from the lot of wire that is to be used for the anode.

# 2.1.4.3 Canister Contained Mixed Metal Oxide Anodes

Canister contained mixed metal oxide anodes shall be packed at the factory in light weight, light gauge steel uni-body TIG welded canisters with calcinated petroleum coke breeze. The canisters shall be capped with TIG welded steel and caps providing a totally encapsulated construction. The connecting cable shall pass through a hole in an end cap designed to be tight fitting with a heavy duty strain relief allowing for handling of the canister by the cable. The anode shall be centered in the canister by centralizers to maintain rod position.

# 2.1.4.4 Anode Connecting Cables

Anodes shall have connecting cables installed at the factory. The connection between the anode rod or ribbon and the lead wire shall be made with a solid crimp couple with solder. The connection shall be sealed in cast epoxy.

#### 2.1.4.5 Canister Connection Cables

Canister connecting cables shall consist of an ultra low resistance solder connection which is a minimum of three times stronger than the cable. For ceramic coated canister anodes, the cable connection shall consist of two molded dielectric layers (pressure seals), a flexible backfill resin encapsulant stabilizer, a schedule 40 PVC pipe Type 1 seal, and Type 1 PVC pipe end plugs. The seals and end plugs shall resist chlorine gas and acid.

# 2.1.4.6 Deep Anode Connection Cables

For deep anode beds, each anode located in the borehole shall be accompanied by a reel of continuous cable having the length indicated. For deep ceramic coated anode beds, anode connecting cables shall have molded multiseal solder connections; splices will not be permitted. Chlorine gas resistant cable and shield shall be used for chlorine environments.

# 2.2 RECTIFIERS AND ASSOCIATED EQUIPMENT

## 2.2.1 Rectifier Unit

Rectifier unit shall consist of a transformer, rectifying elements, transformer tap adjuster, terminal block, one dc output voltmeter, one dc output ammeter, one toggle switch for each meter, fuse holders with fuses for each dc circuit, variable resistors, an ac power-supply circuit breaker, lightning arresters for both input and output, all wired and assembled in a weatherproof cabinet. The overall efficiency of the rectifier shall be not less than 65 percent when operated at nameplate rating and shall be capable of supplying continuous full rated output at an ambient temperature of 112 degrees F in full sunlight with expected life in excess of 10 years. Rectifier output shall be 80 VCDC, 18A.

## 2.2.1.1 Transformer

Transformer shall conform to UL 506.

# 2.2.1.2 Rectifiers

Rectifying elements shall be silicon diodes connected to provide full-wave rectification. Silicon diodes shall be protected by selenium surge cells or varistors against over-voltage surges and by current-limiting devices against over-current surges.

## 2.2.1.3 Meters

Meters shall be accurate to within plus or minus 2 percent of full scale at 80 degrees F, and shall possess temperature stability above and below 80 degrees F and shall possess temperature stability above and below 80 degrees F of at least 1 percent per 10 degrees F. Separate meters shall be 2-1/2 inch nominal size or larger.

## 2.2.1.4 Circuit Breaker

A single -pole, flush-mounted, fully magnetic, properly rated non-terminal type circuit breaker shall be installed in the primary circuit of the rectifier supply transformer.

#### 2.2.1.5 Fuses

Cartridge-type fuses with suitable fuse holders shall be provided in each leg of the dc circuit.

## 2.2.2 Cabinet Construction

Cabinet shall be constructed of not lighter than No. 16 gauge steel , and shall be provided with a full door. The enclosure shall have oil-resistant gasket. The door shall be hinged and have a hasp that will permit the use of a padlock. The cabinet shall be fitted with screened openings of the proper size to provide for adequate cooling. Holes, conduit knockouts, or threaded hubs of sufficient size and number shall be conveniently located.

## 2.2.2.1 Wiring Diagram

A complete wiring diagram of the power unit showing both the ac supply and the dc connections to anodes shall be on the inside of the cabinet door. All components shall be shown and labeled.

# 2.2.2.2 Grounding Provisions

Grounding provisions shall comply with NFPA 70 and UL 467 including a ground terminal in the cabinet. The grounding conductor from the terminal to the earth grounding system shall be solid or stranded copper not smaller than No. 6 AWG. The earth grounding system shall consist of one or more ground rods. Ground rods shall be of copper-clad steel conforming to UL 467 not less than 5/8 inch in diameter by 8 feet in length. Rods shall be driven full length into the earth. Sectional type rods may be used.

# 2.2.2.3 Cabinet Paint System

The cabinet and mounting support shall be painted with the manufacturer's standard painting system.

# 2.2.3 Wiring

Wiring shall be installed in accordance with NFPA 70 utilizing type TW or RHW or polyethylene insulation. Fittings for conduit and cable work shall conform to UL 514A. Outlets shall be of the threaded hub type with gasketed covers. Conduit shall be hub type with gasketed covers. Conduit shall be securely fastened at 8 foot intervals or less. Splices shall be made in outlet fittings only. Conductors shall be color coded for identification. Cable for anode header and distribution shall be No. 6 AWG stranded copper wire with type cathodic protection high molecular weight

polyethylene insulation.

## 2.3 COKE BREEZE

## 2.3.1 Calcined Petroleum Coke Breeze (Dry)

Breeze shall conform to the following requirements:

# 2.3.1.1 Electrical Resistivity

Resistivity shall not exceed 1 milliohm-meter (0.1 ohm-cm) Great Lake Carbon C 12 A Test Method.

# 2.3.1.2 General Backfill Specifications

Bulk Density - 65 to 75 lbs/cubic foot Fixed Carbon - 99.0% or greater Volatiles - 0.2% or less Sizing - 100% less than 1/2 inch

## 2.4 MISCELLANEOUS MATERIALS

#### 2.4.1 Electrical Wire

## 2.4.1.1 Anode Connecting Wire

Anode connecting wire shall be No. 8 AWG stranded copper wire with type CP high molecular weight polyethylene insulation, 7/64 inch thick, 600 volt rating, in accordance with NEMA WC 5. Cable-to-anode contact resistance shall be 0.003 ohms maximum. Deep anode ground bed connecting wire shall be No. 8 AWG, stranded copper wire with an inner jacket of 40 mils of Halar insulation covered by an outer jacket of 65 mils CP high molecular weight polyethylene insulation, 600 volt rating, in accordance with NEMA WC 5. Cable-to-anode contact resistance shall be 0.02 ohms maximum.

## 2.4.1.2 Anode Header Cable

Cable for anode header and distribution shall be No. 6 AWG stranded copper wire with type CP high molecular weight polyethylene, 7/64 inch thick insulation , 600-volt rating, in accordance with NEMA WC 5.

## 2.4.1.3 Test Wires

Test wires shall be No.  $12~{\rm AWG}$  stranded copper wire with NFPA 70 Type TW or RHW or polyethylene insulation.

# 2.4.2 Deep Anode Ground Bed Casing

Casing shall be 10 inch outside diameter, 1/8 inch minimum wall thickness black steel pipe, conforming to ASTM A 53/A 53M, Type E or S, Grade B. The metal casing shall extend no more than 5 feet below the top of a well cap.

# 2.4.3 Anode Centering Device for Deep Anode Ground Beds

Anode centering device shall be nonmetallic and capable of maintaining centering in the hole without interfering with other anode lead wiring, until coke breeze is packed in place.

#### 2.4.4 Conduit

Nonmetallic conduit shall conform to NEMA TC 2.

# 2.4.5 Polyethylene Insulation

Polyethylene insulation shall comply with the requirements of ASTM D 1248 and of the following types, classes, and grades:

# 2.4.5.1 High Molecular Weight Polyethylene

High molecular weight polyethylene shall be Type I, Class C, Grade E5.

## 2.4.6 Test Stations

Test stations shall be complete with an insulated terminal block having the indicated number of terminals and shall be provided with a lockable cover and have a cast-in legend, "C.P. Test". Test stations shall be complete with an insulated terminal block having the required number of terminals. (One terminal required for each conductor). Sufficient test stations to monitor underground isolation points shall be provided. Test-bond stations (potential measurement and stray current control) shall be provided to monitor pipe to soil potential of proposed underground pipes or existing underground metallic structures which may conduct stray current from the new cathodic protection system. The location of the test-bond stations shall ensure that the pipe to soil potential of metallic pipe not designated to be protected is not made less negative by the energization of the cathodic protection system. Test station terminal connections and the terminal conductor shall be permanently tagged to identify each termination of the conductors (e.g. identify the conductors connected to the protected structures). Conductors shall be permanently identified in the station by means of plastic or metal tags, or plastic sleeves to indicate termination. Each conductor shall be color coded in accordance with the drawings. The station test facility, including permanent Cu-Cu S04 reference cells and test returns shall be installed as indicated. Pavement inserts shall be nonmetallic and shall allow Cu-Cu SO4 reference electrode to contact the electrolyte beneath the pavement surface. Abbreviations shall not be used. Welding of electrical connections shall be as follows: Exothermic welds shall be "CADweld", "Thermo-weld", or approved equal. Use and selection of these materials and welding equipment shall be in accordance with the manufacturer's recommendations.

# 2.4.7 Sealing and Dielectric Compound

Sealing and dielectric compound shall be a black, rubber based compound that is soft, permanently pliable, tacky, moldable, and unbacked. Compound shall be applied as recommended by the manufacturer, but not less than 1/8 inch thick.

## 2.4.8 Preformed Sheaths

Preformed sheaths for encapsulating electrical wire splices to be buried underground shall fit the insulated wires entering the spliced joint.

# 2.4.9 Epoxy Potting Compound

Epoxy potting compound for encapsulating electrical wire splices to be buried underground shall be a two package system made for the purpose.

#### 2.4.10 Backfill Shields

Backfill shields shall consist of approved pipeline wrapping or fiberglass reinforced, coal-tar impregnated tape, or plastic weld caps, specifically made for the purpose.

# 2.4.11 Electrical Tape

Pressure-sensitive vinyl plastic electrical tape shall conform to UL 510.

# 2.4.12 Cable Marker Tape

Traceable marker tape shall be manufactured for the purpose and clearly labeled "Cathodic Protection Cable Buried Below".

# 2.4.13 Electrically Isolating Pipe Joints

Electrically isolating pipe joints shall be of a type that is in regular factory production. And shall be as specified under the Mechanical Sections of these specifications.2.5 LEAD WIRE CONNECTIONS

Lead wire to structure connections shall be by exothermic welding process. Weld charges made specifically for use on cast iron shall be used on cast iron pipe. A backfill shield filled with a pipeline mastic sealant or material compatible with the coating shall be placed over the weld connection and shall cover the exposed metal adequately.

## PART 3 EXECUTION

# 3.1 CRITERIA OF PROTECTION

Acceptance criteria for determining the adequacy of protection on a buried pipe shall be in accordance with NACE RP0169, and as specified below.

## 3.1.1 Iron and Steel

The following method a. shall be used for testing cathodic protection voltages. If more than one method is required, method b. shall be used:

- a. A negative voltage of at least minus 850 millivolts as measured between the pipe and a saturated copper-copper sulphate reference electrode contacting the (electrolyte) earth directly over the pipe. Determination of this voltage shall be made with the cathodic protection system in operation. Voltage drops shall be considered for valid interpretation of this voltage measurement. A minimum of minus 850 millivolts "instant off" potential between the pipe being tested and the reference cell shall be achieved over 95 percent of the area of the structure. Adequate number of measurements shall be obtained over the entire structure, pipe, tank, or other metallic component to verify and record achievement of minus 850 millivolts "instant off". This potential shall be obtained over 95 percent of the total metallic area without the "instant off" potential exceeding 1200 millivolts.
- b. A minimum polarization voltage shift of 100 millivolts as measured between the pipe and a saturated copper-copper sulphate reference electrode contacting the earth directly over the pipe . This polarization voltage shift shall be determined by interrupting the protective current and measuring the polarization decay. When the protective current is interrupted, an immediate voltage shift will

occur. The voltage reading, after the immediate shift, shall be used as the base reading from which to measure polarization decay. Measurements achieving 100 millivolts shall be made over 95 percent of the metallic surface.

## 3.1.2 Aluminum

## 3.2 GROUND BED INSTALLATION

## 3.2.1 Shallow Ground Beds

## 3.2.1.1 Cable Protection

Positive cable to the ground bed and negative cable to the pipe to be protected shall be buried a minimum depth of 30 inches except where above ground construction utilizing conduit is used.

## 3.2.2 Deep Anode Ground Beds

Deep anode ground beds shall consist of an installation of anodes supported one above the other and supported in place by a method that does not suspend the anodes from the connecting cable. Deep anode ground beds shall be installed in accordance with NACE RP0572 and as specified in these specifications.

# 3.2.2.1 Anode Centering

Anodes shall be centered in the well by means of centering devices.

## 3.2.2.2 Casing

The casing shall be to a depth and elevation of not more than 10 feet.

# 3.2.2.3 Anode Requirements

Anode sizes, spacing, number of anodes, depth of well, and other details shall be as shown.

# 3.2.2.4 Anode Lead Wire

Each anode shall have a separate, continuous wire extending from the anode to the junction box at the well head.

# 3.2.2.5 Anode Cables

Anode cables shall terminate in a nearby junction box, equipped with individual anode current shunts. Where full length casing is used, two wire connections from casing shall terminate in the junction box.

## 3.2.2.6 Anode and Cable Installation

If the method of installation utilizes backfill support for anodes and cable, slack in the cable near each anode shall be provided and the cable insulation shall be increased in thickness from 7/64 to 5/32 inch utilizing an approved composite of plastic and elastomeric materials.

## 3.2.2.7 Backfill

The well shall be backfilled with calcined petroleum coke breeze or

metallurgical coke breeze surrounding the anodes by a method that does not leave voids or bridging. The recommended method is to pump the backfill from the bottom upward. The well shall be over-filled with coke breeze allowing for settlement so that the settled level after a number of days is as high as the level shown. The number of days allowed for settling of the coke breeze will be determined by the Contracting Officer. If the top level of coke breeze is below the level shown after settlement, additional coke breeze shall be put in the well. The backfill used shall not require tamping. The top portion of the well shall be sealed for 25 feet to prevent surface water run-off. All vents shall be vented above the high water mark and at a safe height.

#### 3.3 MISCELLANEOUS INSTALLATION

# 3.3.1 Rectifier Installation

Mounting shall be as shown.

#### 3.3.2 Wire Connections

### 3.3.2.1 Wire Splicing

Connecting wire splicing shall be made with copper compression connectors or exothermic welds, following instructions of the manufacturer. Split-bolt type connectors shall not be used.

#### 3.3.2.2 Steel Surfaces

Connections to ferrous pipe shall be made by exothermic weld methods as manufactured by an approved manufacturer for the type of pipe . Electric arc welded connections and other types of welded connections to ferrous pipe and structures shall be approved before use.

### 3.3.3 Pipe Joints

#### 3.3.3.1 Electrical Isolation of Structures

Electrical isolation of structures shall be as follows:

a. Isolating Fittings: Isolating flanges and couplings shall be installed aboveground, or within manholes, wherever possible, but an isolating device that electrically separates a pipeline shall not be installed in a confined area where a combustible atmosphere may collect unless precautions are taken to prevent arcing such as by means of externally located surge arresters, grounding cells, or other means. Isolating flanges and couplings in lines entering buildings shall be located at least 12 inches above grade or floor level. Pipelines entering buildings either below or above ground shall be electrically isolated from the structure wall with an electrically isolating wall sleeve.

### 3.3.4 Dissimilar Metals

Buried piping of dissimilar metals including new and old steel piping, excepting valves, shall be electrically separated by means of electrically insulating joints at every place of connection. The insulating joint, including the pipes, shall be coated with an underground type dielectric coating for a minimum distance of 10 diameters on each side of the joint.

### 3.3.5 Casing

Where a pipeline is installed in a casing under a roadway or railway, the pipeline shall be electrically isolated from the casing, and the annular space sealed against incursion of water.

#### 3.3.6 Test Stations

Test stations shall be of the type and location shown and shall be curb box mounted. Changes in designated location shall have prior approval.

#### 3.4 TESTS AND MEASUREMENTS

#### 3.4.1 Baseline Potentials

Each test and measurement will be witnessed by the Contracting Officer. The Contractor shall notify the Contracting Officer a minimum of 5 working days prior to each test. After backfill of the pipe and anodes is completed, but before the anodes are connected to the pipe, the static potential-to-soil of the pipe shall be measured. The locations of these measurements shall be identical to the locations specified for pipe-to-reference electrode potential measurements.

#### 3.4.2 Isolation Testing

Before the anode system is connected to the pipe , an isolation test shall be made at each isolating joint or fitting. This test shall demonstrate that no metallic contact, or short circuit exists between the two isolated sections of the pipe . Any isolating fittings installed and found to be defective shall be reported to the Contracting Officer.

#### 3.4.2.1 Insulation Checker

A Model 601 insulation checker, as manufactured by "Gas Electronics", shall be used for isolating joint (flange) electrical testing ing accordance with anufacturer's operating instructions. An isolating joint that is good will read full scale on the meter; if an isolating joint is shorted, the meter pointer will be deflected at near zero on the meter scale. Location of the fault shall be determined from the instructions and the joint shall be repaired. If an isolating joint is located inside a vault, the pipe shall be sleeved with insulator when entering and leaving the vault.

# 3.4.2.2 Cathodic Protection Meter

A Model B3A2 cathodic protection meter, as manufactured by "M. C. Miller" using the continuity check circuit shall be used for isolating joint (flange) electrical testing. This test shall be performed in addition to the Model 601 insulation checker. Continuity is checked across the isolated joint after the test lead wire is shorted together and the meter adjusted to scale. A full scale deflection indicates the system is shorted at some location. The Model 601 verifies that the particular insulation under test is good and the Model B3A2 verifies that the system is isolated. If the system is shorted, further testing shall be performed to isolate the location of the short.

### 3.4.3 Anode Output

After the rectifier is energized, the current output of the individual

anode leads shall be measured by using an approved method. This may be done with a shunt and MV meter, a low-resistance ammeter, or a clamp-on milliammeter. The total current shall be measured and compared to the sum of all anode currents and to the rectifier output current. If an individual anode output current meets or exceeds the recommended output for that anode, the system shall be turned down or balancing resistors installed. Calculation of the wattage of the resistors shall be sufficient to handle the maximum load which will be encountered on the anode lead. All measurements obtained, the date, time, and locations of all measurements shall be recorded.

#### 3.4.4 Electrode Potential Measurements

Upon completion of the installation and with the entire cathodic protection system in operation, electrode potential measurements shall be made using a copper-copper sulphate reference electrode and a potentiometer-voltmeter, or a direct current voltmeter having an internal resistance (sensitivity) of not less than 10 megohms per volt and a full scale of 10 volts. The locations of these measurements shall be identical to the locations used for baseline potentials. The values obtained and the date, time, and locations of measurements shall be recorded. No less than 8 measurements shall be made over any length of line or component. Additional measurements shall be made at each distribution service riser, with the reference electrode placed directly over the service line.

### 3.4.5 Location of Measurements

# 3.4.5.1 Coated Piping or Conduit

For coated piping or conduit, measurements shall be taken from the reference electrode located in contact with the earth, directly over the pipe or by means of permanent reference electrodes. Connection to the pipe shall be made at service risers, valves, test leads, or by other means suitable for test purposes. Additional measurements shall be made at each distribution service riser, with the reference electrode placed directly over the service line adjacent to the riser. Potentials shall be plotted versus distance to an approved scale. Locations where potentials do not meet or exceed the criteria shall be identified and reported to the Contracting Officer.

#### 3.4.6 Casing Tests

Before final acceptance of the installation, the electrical separation of carrier pipe from casings shall be tested and any short circuits corrected.

# 3.4.7 Interference Testing

Before final acceptance of the installation, interference tests shall be made with respect to any foreign pipes in cooperation with the owner of the foreign pipes. A full report of the tests giving all details shall be made.

# 3.4.8 Recording Measurements

All pipe- to-soil potential measurements including initial potentials where required shall be recorded. The Contractor shall locate, correct and report to Contracting Officer any short circuits to foreign pipes encountered during checkout of the installed cathodic protection system. Pipe- to-soil potential measurements are required on as many pipes as

necessary to determine the extent of protection or to locate short-circuits.

#### 3.5 TRAINING COURSE

The Contractor shall conduct a training course for the operating staff as designated by the Contracting Officer. The training period shall consist of a total of 4 hours of normal working time and shall start after the system is functionally completed but prior to final acceptance tests. The field instructions shall cover all of the items contained in the operating and maintenance instructions, as well as demonstrations of routine maintenance operations, including testing procedures included in the maintenance instructions. At least 14 days prior to date of proposed conduction of the training course, the training course curriculum shall be submitted for approval, along with the proposed training date. Training shall consist of demonstration of test equipment, providing forms for test data and the tolerances which indicate that the system works satisfactorily.

-- End of Section --

### SECTION 15060

### PIPE, MANUAL VALVES, AND FITTINGS, FUELING SYSTEM

# PART 1 GENERAL

#### 1.1 REFERENCES

Waiver to Use MilStds and MilSpecs in Air Force Fuel Projects, HQ AFCESA/CESM (01/29/96.

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

# AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI Z49.1 (1988) Safety in Welding and Cutting

#### AMERICAN PETROLEUM INSTITUTE (API)

API SPEC 5L	(1995) Line Pipe
API SPEC 6D	(1994) Pipeline Valves (Gate, Plug, Ball and Check Valves)
API STD 607	(1993) Fire Test for Soft-Seated Quarter-Turn Valves
API STD 608	(1995) Ball Valves
API RP 1110	(1991) Pressure Testing of Liquid

# AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME-16	(1992; Addenda Dec 1992, Dec 1994) Boiler and Pressure Vessel Code; Section VIII, Pressure Vessels DIVISION 1
ASME-17	(1992; Addenda Dec 1992, Dec 1993, Dec 1994) Boiler and Pressure Vessel Code; Section IX, Welding and Brazing Procedures, Welders, Brazers, and Welding and Brazing Operators
ASME B1.1	(1989) Unified Inch Screw Threads (UN and UNR Thread Form)
ASME/ANSI B 16.34	Valves-Flanged, Threaded and Welding Ends
ASME B16.5	(1996) Pipe Flanges and Flanged Fittings
ASME B16.9	(1993) Factory-Made Wrought Steel

Buttwelding Fittings

ASME B16.11	(1991) Forged Fittings, Socket-Welding and Threaded
ASME B16.21	(1992) Nonmetallic Flat Gaskets for Pipe Flanges
ASME B18.2.1	(1996) Square and Hex Bolts and Screws (Inch Series)
ASME B18.2.2	(1987; R 1999) Square and Hex Nuts (Inch Series)
ASME B31.1	(2001) Power Piping
ASME B31.3	(1990; B31.3a-1990; Errata; B31.3b-1991) Chemical Plant and Petroleum Refinery Piping
AMERICAN SOCIETY OF TES	TING AND MATERIALS (ASTM)
ASTM A53	(1999;a Rev. B) Pipe, Steel, Black and Hot-Dipped, Zinc-Coated Welded and Seamless
ASTM A105	(1996) Forgings, Carbon Steel, for Piping Components
ASTM A181	(1995b) Carbon Steel Forgings, for General Purpose Piping
ASTM A182	(1996e) Forged or Rolled Alloy-Steel Pipe Flanges, Forged Fittings, and Valves and Parts for High-Temperature Service
ASTM A193	(1996b) Alloy-Steel and Stainless Steel Bolting Materials for High-Temperature Service
ASTM A194	(1996) Carbon and Alloy Steel Nuts for Bolts for High-Pressure and High-Temperature Service
ASTM A234	(1996a) Piping Fittings of Wrought Carbon Steel and Alloy Steel for Moderate and Elevated Temperatures
ASTM A269	(1996) Seamless and Welded Austenitic Stainless Steel Tubing for General Service
ASTM A312	(1991c) Seamless and Welded Austenitic Stainless Steel Pipe
ASTM A358	(1995) Electric-Fission-Welded Austonitic
	Chromium-Nickel Alloy Steel Pipe for High-Temperature Service
ASTM A403	(1996) Wrought Austenitic Stainless Steel Piping Fittings

ASTM D229 (1991) Rigid Sheet and Plate Materials Used for Electrical Insulation (1991) Radiographic Testing ASTM E94 ASTM F436 (1993) Hardened Steel Washers AMERICAN WELDING SOCIETY (AWS) AWS A2.4 (1998) Standard Symbols for Welding, Brazing and Nondestructive Examination AWS A3.0 (1994) Standard Welding Terms and Definitions (1991) Carbon Steel Electrodes for AWS A5.1 Shielded Metal Arc Welding AWS A5.4 (1981) Corrosion-Resisting Chromium and Chromium-Nickel Steel Welding Electrodes AWS A5.5 (1981) Low-Alloy Steel Covered Arc Welding Electrodes FEDERAL SPECIFICATIONS (FS) (Rev C) Coating, Pipe, Thermoplastic Resin FS L-C-530 or Thermosetting Epoxy FS L-T-1512 (Rev A; Reinst) Tape, Pressure Sensitive Adhesive, Pipe Wrapping INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE) IEEE C62.41 (1991) Surge Voltages in Low-Voltage AC Power Circuits MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS INDUSTRY (MSS) MSS SP-58 (1993) Pipe Hangers and Supports-Materials, Design and Manufacture MSS SP-69 (1999) Pipe Hangers and Supports-Selection and Application MILITARY SPECIFICATIONS (MS) MS MIL-C-4556 (Rev E) Coating Kit, Epoxy, for Interior of Steel Fuel Tanks (Rev E) Nozzle, Pressure Fuel Servicing, MS MIL-N-5877 Locking, Type D-1, D-2, D-2R Nominal 2-1/2 inch diameter MS MIL-S-13789 (Rev D) Strainers, Sediment: Pipeline, Basket Type

MS MIL-P-24441/GEN (Rev B; Am 1, Supple 1) Paint,

Epoxy-Polyamide

MILITARY STANDARDS (MIL-STD)

(Rev F;1985 Notice 2) Identification MIL-STD-161

Methods Bulk Petroleum Products System

Including Hydrocarbon Missile Fuels

MIL-STD-271 (Rev F) Nondestructive Testing Methods

MIL-STD-24484 (Rev J) Adapter, Pressure Fuel Servicing,

Nominal 2.5 inch diameter

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 30 (1990) Flammable and Combustible Liquids

Code

SOCIETY OF AUTOMOTIVE ENGINEERS (SAE)

SAE J 514 (1989) Hydraulic Tube Fittings, Standard

STEEL STRUCTURES PAINTING COUNCIL (SSPC)

(1995) Power Tool Cleaning SSPC SP 3

SSPC SP 5 (1991) White Metal Blast Cleaning

#### 1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Oualifications of Welders

SD-03 Product Data

Piping; G-AE

Fittings; G-AE

Valves; G-AE

Strainers; G-AE

Epoxy Coating; G-AE

Protective Coatings; G-AE

Sample Connections; G-AE

Isolating Gasket Kits; G-AE

Gaskets; G-AE

SD-06 Test Reports

Pneumatic Test

Hydrostatic Test

SD-07 Certificates

Piping

Fittings

Valves

Qualified Inspector (factory) (owners)

Pipe Weld Radiograph Inspector's Certification (for field welds)

Surface Preparation (interior)

Epoxy Coating and Application

Isolating Gasket Kits

Epoxy Manufacturer's Representative's certification

Survey of final elevation of buried fuel pipe

Survey giving elevation at each joint, elbow, and tee

SD-10 Operation and Maintenance Data

Operation and Maintenance Manuals; G-AO

Operation and maintenance information shall be submitted for the equipment items or systems listed below. Refer to Section 01701 OPERATION AND MAINTENANCE MANUALS for the information to be submitted for various type of equipment and systems.

Manual Valves Strainers Protective Coatings Sample Connections Isolating Gasket Kits Gaskets

### PART 2 PRODUCTS

#### 2.1 DESIGN CONDITIONS

Design conditions shall be as specified in Section 15050 MECHANICAL EQUIPMENT, FUELING SYSTEM.

#### 2.2 MATERIALS

#### 2.2.1 General

Pipe and fittings in contact with fuel shall be stainless steelor interior epoxy coated carbon steel as indicated on the drawings. No zinc coated

metals, brass, bronze or other copper bearing alloys shall be used in contact with the fuel. All carbon steel and stainless steel underground piping shall have a protective coating and shall be cathodically protected in accordance with Section 13112 CATHODIC PROTECTION SYSTEM (IMPRESSED CURRENT). Identification of piping shall be in accordance with MIL-STD-161 unless specified otherwise. Material for manual valves shall be as specified hereinafter.

### 2.2.2 Carbon Steel Piping

Each length of pipe shall be subjected to factory hydrostatic testing and ultrasonic testing in accordance with their respective pipe specification.

- a. Piping 12-Inches and Larger: Seamless, ASTM A53 Grade B having a wall thickness of 0.375-inch.
- b. Piping 2 1/2-Inches through 10-Inches: Seamless, Schedule 40 API SPEC 5L Grade B or ASTM A53 Grade B.
- c. Piping Two-Inches and Smaller: Seamless, Schedule 80 API SPEC 5L Grade B or ASTM A53 Grade B.
- d. Welding Electrodes(Factory Fabrication): E70XX low hydrogen electrodes conforming to AWS A5.1 or AWS A5.5.

## 2.2.2.1 Interior Epoxy Coated Carbon Steel Piping

Interior epoxy coating system shall be factory applied and in accordance with MS MIL-C-4556, six to eight mils dry film thickness. Documentation of conditions during application shall be submitted to the Contracting Officer. Before applying the epoxy coating, the inside of the pipe shall be sandblasted to "white" metal conforming with SSPC SP 5. If the pipe is not internally epoxy lined immediately after cleaning, a rust preventative coating shall be applied. The rust preventative shall be approved by the epoxy manufacturer. The ends of the pipe shall be masked or wiped back a minimum of one inch but not more than one and one-half inches. After the top coat has cured, the internal epoxy lining shall be tested electrically using an approved holiday detector and shall be free of holidays. The ends of the pipe shall then be capped. The shop doing the application shall have a minimum of five years of experience at applying internal epoxy coating. The application and holiday testing at the shop shall be available for inspection at any time by the Contractor or Contracting Officer. The shop shall notify the Contractor and the Contracting Officer at least one week before the pipe and fittings will be cleaned and epoxy coated. The Contractor shall provide a certified technical representative of the epoxy manufacturer to make at least three separate inspection trips with at least one day in the shop per trip. Each trip report shall be submitted to the Contracting Officer.

### 2.2.3 Stainless Steel Piping

- a. Piping 2 1/2-Inches and Larger:
- (1) ASTM A358, Grade 304L, Class 1 or Class 3 with supplementary requirements of S1, S2 and S3, or ASTM A312 Type 304L, seamless (only). Any agreements between the purchaser and the manufacturer or supplier as referenced in the applicable ASTM shall include the Contracting Officer as a party to the agreement. All piping welds will receive 100 percent radiographic inspection, 100 percent liquid penetrant

inspection, 100 percent visual inspection and all tests as required by the applicable ASTM Standard. Piping shall be provided with a nominal wall thickness as shown in Table A for ASTM A358 with the deviation from the nominal wall thickness less than 0.01-inch. ASTM A312 seamless piping shall be provided with a minimum schedule 10S wall thickness.

- (2) Pipe Ends: All Piping shall be provided with beveled ends per Chapter V, ASME B31.3, and shall be shipped with the ends capped.
- (3) Seam and End Welds: All sections of the piping provided shall be accepted on the project site if the seam welds meet the requirements of the paragraph K341 of ASME B31.3 and Appendix 4 of ASME-16. One hundred spots may be reinspected at the project site prior to installation and backfilling at the request of the Contracting Officers Representative. End welds shall be properly aligned prior to welding per Chapter V of the ASME B31.3. Welds found to be defective shall be repaired as per Chapter V of the ASME B31.3 at no additional cost to the government. Observation by the Contracting Officers Representatives of the manufacturing and field procedures shall be allowed under this contract.
- (4) Welders Qualifications: Piping shall be welded in accordance with qualified procedures using performance qualified welders and welding operators. Procedures and welders shall be qualified in accordance with ASME-17. Welding procedures qualified by another employer may be accepted as permitted by ASME B31.1. The Contracting Officer shall be notified 24 hours in advance of tests and the tests shall be performed at the work site if practical. The welder or welding operator shall apply his assigned symbol near each weld he makes as a permanent record.
- (5) Factory Testing and Inspection Records: Per Table K341.3.2A of Chapter VII of ASME B31.3, visual, radiographic and liquid penetrant tests shall be performed for each section of piping provided as all sections are subjected to cyclic conditions. All testing and inspections records shall be submitted to the Contracting Officers Representative and shall indicate the pipe mark and installed location of what piping section on the project site. Observation by the contracting Officers Representatives of the manufacturers and the fields testing and inspection procedures shall be allowed under this contract. Pipe certification along with pipe markings shall be submitted before the pipe arrives on the job site.
- (6) Welding Inspectors for Stainless Steel Piping: The contractor shall submit the qualifications of all the testing personnel that will perform all field tests as requested by the Contracting Officer. The qualifications of all personnel on the job site that will perform welding inspection shall be submitted for approval. These inspectors shall meet the qualifications as defined in Chapter VI of the ASME B31.3, and may use the methods as defined in Table K341.3.2 B of the ASME B31.3.
- (7) The Contractor shall provide a qualified inspector (factory) in accordance with Chapter VI of ASME B31.3. to act as the owner's inspector (for the Government) at the pipe manufacturer's facility in addition to the manufacturer's inspector.
- (8) Quality Assurance Plan shall be submitted for the welding, inspecting and testing of the welded seam pipe.

TABLE A

Nominal	Nomin	nal (Average)
Pipe Size	Pipe O.D.	Wall Thickness(tn)
12 in.	12.750 in.	0.250 in.
10 in.	10.750 in.	0.250 in.
8 in.	8.625 in.	0.250 in.
6 in.	6.625 in.	0.219 in.
4 in.	4.500 in.	0.219 in.
2 1/2 in.	2.875 in.	0.156 in.

- b. Piping Two-Inches and Smaller: Schedule 80 ASTM A312 seamless Type 304L for threaded piping and schedule 40 (unless otherwise indicated) ASTM A312 seamless Type 304L for welded piping.
- c. Stainless Steel Control Tubing: Seamless, fully annealed tubing conforming to ASTM A269, Grade TP316, Rockwell hardness B80 or less. Wall thickness for 1/2-inch tubing to be 0.049-inch.
- d. Welding Electrodes (Factory Fabrication): E308L conforming to AWS A5.4.

### 2.2.4 Protective Coatings for Aboveground Carbon Steel Piping

Provide coating of aboveground piping, piping in pits, pipe supports, filter separators, and miscellaneous metal and equipment in accordance with MS MIL-P-24441/GEN and the instructions that follow. Color of finish coat shall be white. Do not paint stainless steel or aluminum surfaces. Surfaces including those that have been shop coated, shall be solvent cleaned. Surfaces that contain loose rust, loose mill scale, and other foreign substances shall be cleaned mechanically with power tools according to SSPC SP 3. Cleaning shall be performed in sections or blocks small enough to permit application of the epoxy-polyamide prime coat during the same work shift. Shop-coated surfaces shall be protected from corrosion by treating and touching up corroded areas immediately upon detection.

### 2.2.4.1 Coating Description

Epoxy-polyamide coatings consist of a two component system that includes a pigmented polyamide resin portion (A component) and an epoxy resin portion (B component). Once they are mixed together and applied as a paint film, the coating cures to a hard film by chemical reaction between the epoxy and polyamide resins. Epoxy-polyamide coating (MS MIL-P-24441/GEN) consists of individual formulations, for example, Formula 150 is for green primer, and Formula 152 is for white topcoat.

# 2.2.4.2 Mixing Epoxy-Polyamide Coatings

Epoxy-polyamide coatings are supplied in measured amounts that must be mixed together in exact proportions to ensure the correct and complete chemical reaction. Mix no more paint than can be applied in the same day. The estimated pot life is 3-4 hours for 5 gallons at  $70-80^{\circ}$  F. Discard any mixed paint remaining at the end of the day.

a. Mixing Ratio. The mixing ratio of the MS MIL-P-24441/GEN coatings (except Formula 159) are all 1:1 by volume, for example, 5 gallons of component A to 5 gallons of component B. The mixing ratio of

MS MIL-P-24441/GEN for formula 159 is 1:4 by volume.

b. Mixing Procedures. Each component shall be thoroughly stirred prior to mixing the components together. After mixing equal volumes of the two components, this mixture shall again be thoroughly stirred until well blended. The induction time shall be adhered to, to ensure complete chemical reactions. Induction time is defined as the time immediately following the mixing together of components A and B during which the critical chemical reaction period of these components is initiated until the mixture is ready for application. This reaction period is essential to ensure the complete curing of the coating. Volumetric mixing spray equipment with in-line heaters set at 70 to 80° F (21 to 28° C) may be used without an induction period.

#### 2.2.4.3 Induction Times

The temperature of the paint components in storage should be measured to determine induction time and pot life. Pot life is the usable life of the mixed paint. It is dependent upon the temperature and the volume of the mixed paint. The pot life of a five gallon mixture of the MS MIL-P-24441/GEN paints at 70-80EF is approximately 4 hours. The job site application temperature will affect the time required for the paint to cure, and must be considered in estimating induction time, cure time, and the effect of batch size on these functions. At 40 to  $60^{\circ}$  F a 1 hour induction time shall be used. Volumetric mixing spray equipment with in-line heaters set at 70 to  $80^{\circ}$  F may be used without an induction period. To ensure that the reaction proceeds uniformly, the paint should be manually stirred periodically during its induction period. This prevents localized overheating or hot spots within the paint mixture.

#### 2.2.4.4 Epoxy-Polyamide Coating Application

Epoxy-polyamide coatings, MS MIL-P-24441/GEN, may be applied by brushing or spraying.

- a. Thinning Application. Ordinarily, MS MIL-P-24441/GEN coatings are not thinned. If necessary, up to one pint of epoxy thinner for each gallon of mixed paint may be added if paint has thickened appreciably during cold temperature application or if necessary to improve application characteristics. When applied at the proper thickness, without thinning, these paints will have no tendency to sag.
- b. Application Thickness. Unless otherwise specified, apply each coat of paint to produce approximately 3 mils dry film thickness (DFT). Application which yields in excess of 4.0 mils DFT should be avoided to prevent sagging.
- c. Spray Application. MS MIL-P-24441/GEN paints should be sprayed with conventional spray guns and normal spray-pot pressures. The spray gun should be equipped with a middle-size (D) needle, and nozzle setup. Both conventional and airless spray equipment are suitable for use with or without volumetric mixing capability.

# 2.2.4.5 Equipment Cleanup

The mixed paint should not be allowed to remain in spray equipment for an extended period, especially in the sun of a warm area. The paint cures

more rapidly at higher temperatures. When components A and B are mixed together, the pot life of the mixture (including the induction time is 6 hours at  $70^{\circ}$  F ( $21^{\circ}$  C). Pot life is longer at lower temperatures and shorter at temperatures above  $70^{\circ}$  F ( $21^{\circ}$  C). Spray equipment should be cleaned after using by flushing and washing with epoxy thinner or aromatic hydrocarbon thinners (xylene or high flash aromatic naphtha). General cleanup is also done by using these solvents. Brushes and rollers should be given a final cleaning in warm soapy water, rinsed clean with warm fresh water and hung to dry.

# 2.2.5 Protective Coatings for Buried Steel Piping

Provide pipe with FS L-C-530 coating system of factory-applied adhesive undercoat and continuously extruded plastic resin coating; minimum thickness of plastic resin shall be 36 mils for pipe sizes 6 inches and larger. Fittings, couplings, irregular surfaces, damaged areas of pipe coating, and existing piping affected by the Contractor's operations shall be clean, dry, grease free, and primed before application of tape. Tape shall overlap the pipe coating not less than three inches. Waterproof shrink sleeves may be provided in lieu of tape and shall overlap the pipe coating not less than six inches. Pipe coating and adhesive undercoat surfaces to be wrapped with tape shall be primed with a compatible primer prior to application of tape. Primer shall be as recommended by tape manufacturer and approved by pipe coating manufacturer.

- a. Damaged Areas of Pipe Coating: Provide FS L-T-1512, 20 mils nominal thickness of tape over damaged areas. Residual material from damaged areas of pipe coating shall be pressed into the break or trimmed off. Apply tape spirally with one-third overlap as tape is applied. A double wrap of one full width of tape shall be applied at right angles to the axis to seal each end of the spiral wrapping.
- b. Fittings, Couplings, and Regular Surfaces: Provide FS L-T-1512, 10 mils nominal thickness tape overlapped not less than 1.0 inch over damaged areas. Initially stretch and apply first layer of tape to conform to component's surface. Then apply and press a second layer of tape over first layer of tape.
- c. Testing of Protective Coatings: Perform tests with an approved silicone rubber electric wire brush or an approved electric spring coil flaw tester. Tester shall be equipped with an operating bell, buzzer, or other audible signal which will sound when a holiday is detected at minimum testing voltage equal to 1,000 times the square root of the average coating thickness in mils. Tester shall be a type so fixed that field adjustment cannot be made. Calibration by tester manufacturer shall be required at six-month intervals or at such time as crest voltage is questionable. Certify in writing the calibration date and crest voltage setting. Maintain the battery at ample charge to produce the crest voltage during tests. Areas where arcing occurs shall be repaired by using material identical to original coating or coating used for field joints. After installation, retest the exterior surfaces, including field joints, for holidays. Promptly repair holidays.

#### 2.2.6 Fittings

#### 2.2.6.1 General

Welding ells, caps, tees, reducers, etc., to be of materials compatible for welding to the pipe line in which they are installed, and wall thickness, pressure and temperature ratings of the fittings shall be not less than the adjoining pipe line. Unless otherwise required by the conditions of installation, all elbows shall be the long radius type. Miter joints shall not be acceptable. Make odd angle offsets with pipe bends or elbows cut to the proper angle. Butt weld fittings to be factory-made wrought fittings manufactured by forging or shaping. Fabricated fittings will not be permitted. Welding branch fittings shall be insert type suitable for radiographic inspections specified herein.

# 2.2.6.2 Carbon Steel Fittings

- a. Fittings 2-1/2 Inches and Larger: Butt weld, conforming to ASTM A234, grade WPB and ASME B16.9 of the same wall thickness as the adjoining pipe. All welds shall be radiographically examined throughout the entire length of each weld. Each fitting shall be subjected to the Supplementary Requirements S3 and S4, Liquid Penetration examination and Magnetic-Particle Examination. Detectable flaws will not be accepted in the supplementary examinations. Fittings shall be identified to relate them to their respective radiograph.
- b. Fittings 2 Inches and Smaller. Forged (socket welded or if indicated on drawings, threaded), 2,000-pound W.O.G., conforming to ASTM A105, Grade 2 and ASME B16.11. Threaded fittings shall only be used for above grade applications. Underground low point drain pipe and high point vent pipe shall be butt welded.
- c. Flanges: One-hundred-fifty-pound weld neck, forged flanges conforming to ASTM A181, Class 70, and ASME B16.5. Flanges to be 1/16-inch raised face with phonographic finish, except where required otherwise to match equipment furnished. Match flange face to valves or equipment furnished. Flange face shall be machined to match valves or equipment furnished. Use of spacing rings or gaskets discs are not allowed. Flanges shall be subjected to the Supplementary Requirements S4 and S5, Liquid Penetrant Examination, and Magnetic-Particle Examination. Detectable flaws will not be accepted.
- d. Interior Epoxy Coating System shall be applied to the fittings as specified in paragraph "Carbon Steel Piping."

### 2.2.6.3 Stainless Steel Fittings

- a. Fittings 2-1/2 Inches and Larger: Butt weld stainless steel conforming to ASTM A403, Class WP, Type 304L, seamless or welded, and ASME B16.9 of the same minimum wall thickness as the adjoining pipe. Welded fittings shall be tested and inspected the same as the welded seam pipe and meet the same requirements as for the pipe.
- b. Fittings 2-Inches and Smaller: Forged Type 304 or 304L (socket welded or if indicated on drawings, threaded), 2,000-pound W.O.G. conforming to ASTM A182 and ASME B16.11. Threaded fittings shall only be used for above grade applications. Underground low point drain pipe and high point vent pipe shall be butt welded.

- c. Unions. Conforming to ASTM A312, Grade 304 or 316.
- d. Flanges. One-hundred-fifty-pound weld neck, forged Type 304 stainless steel flanges conforming to ASTM A182 and ASME B16.5, except flanges that are to be connected to the fueling/defueling pumps shall be 300-pound. Flanges to be 1/16-inch raised-face with phonographic finish, except where required otherwise to match equipment furnished. Match flange face to valves or equipment furnished. Flanges shall be subjected to the Supplementary Requirements S4, Liquid Penetrant Examination.
- e. Stainless Steel Tube Fittings. Flareless, 316 stainless steel fittings conforming to SAE J 514.

### 2.2.6.4 Isolating Gasket Kits (Insulating) for Flanges

Provide ASTM D229 electrical insulating material of 1,000 ohms minimum resistance; material shall be resistant to the effects of aviation hydrocarbon fuels. Provide full face insulating gaskets between flanges. Provide full surface 0.03-inch thick wall thickness, spiral-wound mylar insulating sleeves between the bolts and the holes in flanges; bolts may have reduced shanks of a diameter not less than the diameter at the root of threads. Provide 0.125-inch thick high-strength phenolic insulating washers next to flanges and provide flat circular stainless steel washers over insulating washers and under bolt heads and nuts. Provide bolts 0.5-inch longer than standard length to compensate for the thicker insulating gaskets and the washers under bolt heads and nuts. Exterior above grade flanges separated by electrically isolating gasket kits shall be provided with weatherproof lightning surge arrester devices. The surge arrester shall bolt across flanges separated by insulating gasket kits per detail on contract drawings. The arrestor shall have the following features:

- a. Weatherproof NEMA 4 enclosure.
- b. Bidirectional and bipolar protection.
- c. Constructed of solid state components, no lights, fuses or relays shall be used that will require maintenance or replacement.
- d. Withstand unlimited number of surges at 50,000 Amperes.
- e. Maximum clamping voltage of 700 Volts based on a IEEE C62.41 8x20 microsecond wave form at 50,000 Amperes peak measured at the device terminals (zero lead length).
- f. A UL listed arrester for installation in Class 1, Division 1 or 2 (as indicated), Group D, hazardous area.

Install the mounting bracket and leads on the flange side of the bolt insulating sleeve and washer, and size in accordance with this schedule.

Line Size (Inches)	Bolt Size	(Inches)
2 2-1/2		5/8
3		5/8 5/8
<u>4</u> 6		5/8 3/4
8		3/4
10		7/8
12		7/8

(Note: Allowance must be made for the 1/32-inch thickness of the insulating sleeve around the bolts when sizing the mounting lugs.)

Provide insulation flanges or unions wherever pipe transitions from underground to aboveground. Not all insulating flanges may be shown on the drawings.

#### 2.2.7 Bolts and Nuts

Bolts and nuts for pipe flanges, flanged fittings, valves and accessories shall conform to ASME B18.2.1 and ASME B18.2.2, except as otherwise specified. Bolts shall be of sufficient length to obtain full bearing on the nuts and shall project no more than two full threads beyond the nuts with the bolts tightened to the required torque. Bolts shall be regular hexagonal bolts conforming to ASME B18.2.1 with material conforming to ASTM A193 B8 Class 2 (Strain Hardened). Bolts shall be threaded in accordance with ASME B1.1, Class 2A fit, Coarse Thread Series, for sizes one inch and smaller and Eight-Pitch Thread Series for sizes larger than one inch. Nuts shall conform to ASME B18.2.2, hexagonal, heavy series with material conforming to ASTM A194, Grade 8. Nuts shall be threaded in accordance with ASME B1.1, Class 2B fit, Coarse Thread Series for sizes one inch and smaller and Eight-Pitch Thread Series for sizes larger than one inch. Provide washers under bolt heads and nuts. Washers to be ASTM F436, flat circular stainless steel. Torque wrenches shall be used to tighten all flange bolts to the torque recommended by the gasket manufacturer. Tightening pattern shall be as recommended by the gasket manufacturer. Anti-seize compound shall be used on stainless steel bolts.

#### 2.2.8 Gaskets

ASME B16.21, composition ring, using a Buna-N binder, 0.1250-inch thick. Gaskets shall be resistant to the effects of aviation hydrocarbon fuels and manufactured of fire-resistant materials. Full-face gaskets shall be used for flat-face flanged joints. Ring gaskets shall be used for raised-face flanged joints. Gaskets shall be of one piece factory cut.

# 2.2.9 Relief and Drain System Piping

Pressure relief valve discharge lines and drain lines to the product recovery tank shall be Schedule 40 ASTM A312 seamless Type 304L Stainless Steel.

#### 2.2.9.1 Gaskets

See Gaskets specified herein before.

### 2.2.10 Field Applied Protective Coatings

The field joints and fittings of all underground piping shall be coated as herein specified.

### 2.2.10.1 Welded Joints

Heat shrinkable radiation-cross-linked polyolefin wraparound type sleeves shall be applied to all welded joints. Joints shall not be coated until pressure testing is complete. Apply sleeves consisting of 40 mil polyolefin backing and 40 mil thermoplastic mastic adhesive in accordance with the manufacturer's instructions.

### 2.2.10.2 Fittings

Fittings and other irregular surfaces shall be tape wrapped. The tape shall be a plastic mastic laminated tape having 6 mil plastic backing of either polyethylene or polyvinylchlorine and 29 to 44 mil of synthetic elastomer.

#### 2.2.11 Threaded Joints

Threaded joints, if indicated on the drawings, shall be made tight with manufacturer recommended teflon tape or a mixture of graphite and oil, inert filler and oil, or with a graphite compound, applied with a brush to the male threads. Not more than three threads shall show on made up joints. Threaded joints, mechanical couplings and flanges will not be permitted in buried piping. Threaded joints shall not get welded.

#### 2.2.12 Welded Joints

Welded joints in steel pipe shall be as specified in Part 3 "EXECUTION."

### 2.3 MANUAL VALVES

All portions of a valve coming in contact with fuel in stainless steel pipe lines shall be of noncorrosive material. Valves in stainless steel pipe lines shall be Type 304 or Type 316 stainless steel or carbon steel internally plated with chromium or nickel or internally electroless nickel plated. Stem and trim shall be stainless steel for all valves. Manually operated valves six inches and larger shall be worm-gear operated and valves smaller than six inches shall be wrench operated. Valves smaller than two inches shall have lever-type handles, except small globe valves shall have handwheel operators. Valves installed more than eight (8) feet above finished floor shall have chain operators and a position indicators visible from ground level. Sprocket wheel for chain operator shall be aluminum.

#### 2.3.1 Ball Valves

Ball valves shall be fire tested and qualified in accordance with the requirements of API STD 607 and API STD 608. Ball valves shall be nonlubricated valves that operate from fully open to fully closed with 90 degree rotation of the ball. Valves two inches and larger shall conform to applicable construction and dimension requirements of API SPEC 6D, ANSI Class 150 and shall have flanged ends. Valves smaller than 2 inches shall be ANSI class 150 valves with one piece bodies with flanged ends, unless noted otherwise. The balls in valves 10 inches full port and 12 inch regular port and larger shall have trunnion type support bearings. Except as otherwise specified, reduced port or full port valves may be provided at the Contractor's option.

#### 2.3.1.1 Materials

Ball shall be stainless steel. Ball valves shall have tetrafluoroethylene (TFE) or Viton seats, body seals and stem seals. Valves 2 inches and smaller shall have a locking mechanism.

# 2.3.2 Plug (Double Block and Bleed) Valves

API SPEC 6D, Type III, ANSI Class 150, non-lubricated, resilient, double seated, trunnion mounted, tapered lift plug capable of two-way shutoff.

Valve shall have stainless steel or carbon steel body with chrome-plated interior, tapered plug of steel or ductile iron with chrome or nickel plating and plug supported on upper and lower. Sealing slips shall be steel or ductile iron, with Viton seals which are held in place by dovetail connections. Valve design shall permit sealing slips to be replaced from the bottom with the valve mounted in the piping. Valves shall operate from fully open to fully closed by rotation of the handwheel to lift and turn the plug. Valves shall have weatherproof operators with mechanical position indicators. Minimum bore size shall be not less than 65 percent of the internal cross sectional area of a pipe of the same nominal diameter unless bore height of plug equals the nominal pipe diameter and manufacturer can show equal or better flow characteristics of the reduced bore size design.

### 2.3.2.1 General

Valves in the operating tank suction lines shall be provided with a factory-installed limit switch that is actuated by the valve closure. Each switch shall have one double pole double throw contacts, and shall be watertight and U.L. listed for Class I, Division 1, Group D hazardous areas with (T2D-419 F) temperature limitation.

#### 2.3.2.2 Valve Operation

Rotation of the handwheel toward open shall lift the plug without wiping the seals and retract the sealing slips so that during rotation of the plug clearance is maintained between the sealing slips and the valve body. Rotation of the handwheel toward closed shall lower the plug after the sealing slips are aligned with the valve body and force the sealing slips against the valve body for positive closure. When valve is closed, the slips shall form a secondary fire-safe metal-to-metal seat on both sides of the resilient seal. Plug valves located in Isolation Valve Pits shall be provided with handwheel extensions.

# 2.3.2.3 Relief Valves

ANSI Class 150. Provide plug valves with automatic thermal relief valves to relieve the pressure build up in the internal body cavity when the plug valve is closed. Relief valves shall open at 25 psi differential pressure and shall discharge to the throat of, and to the upstream side, of the plug valve.

#### 2.3.2.4 Bleed Valves

ANSI Class 150, stainless steel body valve. Provide manually operated bleed valves that can be opened to verify that the plug valves are not leaking when in the closed position.

### 2.3.3 Swing Check Valves

Swing check valves shall conform to applicable requirements of API SPEC 6D, regular type, ANSI Class 150 with flanged end connections. Check valves shall be tilting disc, non-slam type with 316 stainless steel body and trim. Discs and seating rings shall be renewable without removing the valve from the line. The disc shall be guided and controlled to contact the entire seating surface.

### 2.4 BALL CHECK RELIEF VALVES

Stainless steel body, ball, and spring ASME/ANSI B 16.34, 3/4" diameter. Valve shall be in-line pattern, spring loaded with fully guided ball and renewable viton seats. Spring shall be factory set at 10 psig.

#### 2.5 ADJUSTABLE RELIEF VALVES

Relief valves shall be the fully enclosed, spring loaded, angle pattern, single port, hydraulically operated type with plain caps, and shall be labeled in accordance with ASME-16. Valve stems shall be fully guided between the closed and fully opened positions. The valves shall be factory-set to open at the set pressure indicated on the drawings. Operating pressure shall be adjustable by means of an enclosed adjusting screw. The valves shall have a minimum capacity of 20 GPM at 10 percent overpressure and shall operate at rated capacity with a back pressure not exceeding 50 psi. Valves shall have a replaceable seat.

#### 2.5.1 Materials

Valves shall have carbon steel bodies and bonnets with stainless steel springs and trim. Valves shall be Class 150 flanged end connections.

### 2.5.2 Sight Flow Indicators

Sight flow indicators shall be ANSI Class 150 and shall have flanged end connections. Sight flow indicators shall consist of a housing containing a rotating propeller that is visible through a glass observation port. The housing shall be stainless steel when installed in stainless steel lines and carbon steel when installed in carbon steel lines. The glass in the indicator shall also meet the Class 150 rating. The indicator down stream of the Pressure Control Valve (PCV) shall contain a bi-directional flapper instead of a propeller.

#### 2.6 PIPING ACCESSORIES

### 2.6.1 Pipe Sleeves

Pipe sleeves shall be installed at all points where the piping passes through concrete construction. Such sleeves shall be of sufficient inside diameter to provide a minimum clear distance between the pipe and the sleeve of 1/2-inch. Sleeves through concrete pits or slabs shall be standard weight carbon steel pipe with a protective coating. Each sleeve shall extend through the respective pit wall or slab and shall be provided with a Buna-N casing seal. Sleeves where piping passes under roads or piping indicated to be double walled shall be standard weight carbon steel pipe with a protective coating as previously specified. Alignment of the sleeve and piping shall be such that the pipe is accurately centered within the sleeve by a nonconductive centering element. The sleeve shall be securely anchored to prevent dislocation. Closure of space between the pipe and the pipe sleeve shall be by means of a mechanically adjustable segmented elastomeric seal. The seal shall be installed so as to be flush.

### 2.6.2 Strainers

### 2.6.2.1 Basket Type

Strainer shall be in compliance with MS MIL-S-13789, except as specified otherwise. Strainer end connections shall be designed in accordance with ASME B16.5, Class 150. Strainers shall have stainless steel bodies, stainless steel shall be Types 304 or 316. Strainers shall have removable

baskets of 60 mesh wire screen with larger wire mesh reinforcement; wire shall be stainless steel, Type 316. Pressure drop for clean strainer shall not exceed three psig at maximum design flow rate. The ratio of net effective strainer area to the area of the connecting pipe shall be not less than three to one. Each strainer shall be provided with a suitable drain at the bottom, equipped with a ball valve. Strainer shall be the single inlet, single outlet design.

Strainer shall be supplied with a piston type direct reading differential pressure gage. The gauge shall consist of a spring-supported, corrosion resistant piston moving inside a glass cylinder, with high pressure applied on top of the piston and low pressure applied below it. Under a differential pressure of 30 PSI, leakage past the piston shall not exceed 120 drops per minute. The cylinder shall have stainless steel and flanges with Viton O-ring seals. The high pressure inlet of the gauge shall have a 10-micron pleated paper filter and the low pressure connection shall have a fine mesh stainless steel strainer. The gauge shall have an operating pressure of 300 PSI. Differential pressure range of the gauge through approximately 3 inches of piston movement shall be 0-30 PSI with an accuracy of + 0.5 PSI, calibrated linearly with one PSI scale graduations. High and low pressure connections shall be 1/4 inch NPT female with a stainless steel bar stock valve at each connection. Construction of the gauge shall be such that a 3-valve manifold is not necessary. If only one bar stock valve is closed, the gauge shall not be damaged by up to 300 PSI differential pressure in either direction.

# 2.6.2.2 Cone Type (Temporary)

Strainer shall be stainless steel type 304 or 316, 60 mesh screen with the ratio of net open area of strainer to the area of the connecting pipe shall be not less than one to one.

# 2.6.3 Pipe Hangers and Supports

# 2.6.3.1 General

Pipe hangers and supports shall conform to MSS SP-58 and MSS SP-69. Supports shall be provided at the indicated locations. Support channels for drain lines shall be epoxy coated on all surfaces or hot-dip galvanized after the channels are cut to length. Coated supports shall be coated with fusion bonded epoxy resin applied by the fluidized bed method. Thickness of the coating shall be not less than 10 mils. Surface preparation and coating application shall be in accordance with the epoxy manufacturer's instructions. The coating shall be pinhole free when tested with a low voltage holiday detector set at no more than 100 times the mil thickness of the coating. All pinholes shall be marked, repaired and retested to ensure a pinhole free film. The coating material shall be a 100 percent solids, thermosetting, fusion-bonded, dry powder epoxy resin. The manufacturer shall certify that the material is suitable for fluidized bed application and that it is approved by the Environmental Protection Administration.

# 2.6.3.2 Adjustable Pipe Supports

Adjustable pipe supports shall consist of a cast iron saddle and a threaded nipple connected to a carbon steel pipe by means of a special reducer conforming to MSS SP-69. The supports shall be provided with neoprene insulation strips.

### 2.6.3.3 Low Friction Supports

Low friction supports shall be self-lubricating antifriction element composed of reinforced TFE. Units shall be factory designed and manufactured.

#### 2.6.3.4 Concrete and Grout

Concrete and grout for anchors and supports shall comply with SECTION 03300 CAST-IN-PLACE STRUCTURAL CONCRETE.

### 2.6.4 Sample Connections

Sample connections shall be factory assembled units specifically designed for obtaining representative samples from fuel pipelines. Each connection shall include a 1/4-inch sampling probe where the probe faces upstream, ball valve and 1/4-inch quick disconnect coupling with dust plug, all assembled into a unit that is suitable for installation in a pipe nipple. The sampling probe shall extend not less than one inch into the fuel pipe. All materials in the sample connections shall be stainless steel or aluminum.

# 2.6.4.1 Sampling Hoses

Furnish two sampling hose assemblies to the Contracting Officer at the project site. Each assembly shall consist of a six-foot length of 1/4-inch clear plastic tubing with internal bonding/grounding wire. One end of the tubing will contain a male connector that actuates flow when inserted into the quick disconnect coupler. Each end of the bonding/grounding wire shall be equipped with clips for attaching to the pipe and metal sample container.

# 2.6.5 Monitoring Points

At the following locations, provide half-inch pipe, flanged ball valve, and blind flange for future test equipment connections:

- a. At the Hydrant Host Truck Checkout, inlet to Hydrant Valve.
- b. At the inlet to the Back Pressure Control Valve in the Pumphouse.
- c. At both sides of the isolation valve in all the isolation valve pits.

### 2.6.6 Pressure Fueling Nozzle

Nozzles shall conform to MS MIL-N-5877, Type D-2. Nozzles and nozzle components shall be compatible with the fuel to be handled. Nozzles shall be provided with an internal 60 mesh stainless steel strainer and a fuel sample connection tapping. Nozzle design shall be for single point fueling of aircraft. Nozzles shall be provided with a compatible dry break quick disconnect swivel. Coupler shall allow for quick disconnect and reconnect of fueling nozzles with corresponding adapters. Coupler and adapter shall provide a positive, leak proof connection under constant or surge flow. Coupler shall be designed to prevent blowout of internal poppet.

# 2.6.7 Nozzle Adapter (SPR)

Adapter shall be a nominal 2-1/2 inches with self-closing valve in accordance with MIL-STD-24484. Adapter shall have a 4 inch flange mounting and metal sealing, vacuum tight, locking dust cap using the SPR lugs.

#### 2.7 FLEXIBLE HOSES

Flexible hoses for fueling pumps shall have ANSI Class 300 flanges of stainless steel construction conforming to ASME B16.5. Flexible hoses shall be of stainless steel flexible metal hose consisting of an inner corrugated stainless steel tube with stainless steel braid cover. All components to be suitable for not less than 275 psig. Length and application of flexible hoses shall be per manufacturer's written recommendations.

#### PART 3 EXECUTION

#### 3.1 WELDING

### 3.1.1 General

All joints unless indicated otherwise, in carbon steel and stainless steel piping systems shall be welded. Unless otherwise approved, all girth welds shall be complete penetration groove welds made in accordance with qualified welding procedures. Welding operations, qualifications of welders and welding procedures shall comply with the provisions of ASME B31.3 and the requirements specified herein.

The root pass on stainless steel and carbon steel pipe shall be by the GMAW or GTAW process.

- a. Definitions shall be in accordance with AWS A3.0.
- b. Symbols shall be in accordance with AWS A2.4 for welding and nondestructive testing, unless otherwise indicated.
- c. Safety Precautions shall conform to ANSI Z49.1.
- d. Weld Preparation shall comply with the requirements of ASME B31.3 and the qualified Welding Procedure Specification. The use of "rice paper" as purge blocks is not permitted. Contractor shall submit alternate method for approval. Back purge gas shall be used for the root pass of all pipe welds.
- e. Backing Rings. The use of backing rings for making or repairing welds will not be permitted.

### 3.1.2 Qualifications of Welders

Welders and welding procedures shall be qualified in accordance with requirements of ASME B31.3.

#### 3.1.2.1 Weld Identification

Each qualified welder shall be assigned an identification symbol. All welds shall be permanently marked with the symbol of the individual who made the weld.

#### 3.1.2.2 Defective Work

Welders found making defective welds shall be removed from the work or shall be required to be requalified in accordance with ASME B31.3.

#### 3.1.3 Tests

All steel pipe field welds, including high point vent pipe and low point drain pipe, shall be examined by radiographic methods to determine conformance to the paragraph "Standards of Acceptance." The services of a qualified commercial or testing laboratory approved by the Contracting Officer shall be employed by the Contractor for testing of piping welds. Costs of testing, including retesting or repaired welds, shall be borne by the Contractor.

### 3.1.3.1 Radiographic Inspection

Procedures for radiographic inspection shall be in accordance with MIL-STD-271 or ASTM E94. Weld ripples or surface irregularities that might mask or be confused with the radiographic image of any objectional defect shall be removed by grinding or other suitable mechanical means. The weld surface shall be merged smoothly with the base metal surface.

### 3.1.4 Standards of Acceptance

Interpretation of test results and limitations on imperfections in welds shall comply with the requirements for 100 percent Radiography, per ASME B31.3, Chapter VII, Table K341.3.2A.

#### 3.1.5 Corrections and Repairs

Defects shall be repaired in accordance with approved procedures. Defects discovered between passes shall be repaired before additional weld material is deposited. Whenever a defect is removed and repair by welding is not required, the affected area shall be blended into the surrounding surface so as to avoid sharp notches, crevices, or corners. After a defect is thought to have been removed, and prior to rewelding, the area shall be examined by suitable methods to insure that the defect has been eliminated. After repairs have been made, the repaired area shall be reinspected and shall meet the standards of acceptance for the original weld. Any indication of a defect shall be regarded as a defect unless reevaluation by nondestructive methods and/or by surface conditioning shows that no defect is present.

#### 3.1.5.1 Defect Removal

Defective or unsound weld joints shall be corrected by removing and replacing the entire weld joint, or for the following defects corrections shall be made as follows:

- a. Excessive Convexity and Overlap: Reduce by removal of excess metal.
- b. Excessive Concavity of Weld, Undersized Welds, Undercutting: Clean and deposit additional weld metal.
- c. Excessive Weld Porosity, Inclusions, Lack of Fusion, Incomplete Penetration: Remove defective portions and reweld.
- d. Crack in Weld or Base Metal: Remove crack throughout its length, including sound weld metal for a distance of twice the thickness of the base metal or two inches, whichever is less, beyond each end of the crack, followed by the required rewelding. Complete

removal shall be confirmed by magnetic particle inspection for carbon steel or liquid penetrant inspection for stainless steel. Inspection procedures shall comply with the requirements of ASME B31.3.

- e. Poor Fit-Up: Cut apart improperly fitted parts, and reweld.
- f. Slag: No slag shall be remaining on the interior of the pipe weld.

# 3.1.5.2 Methods of Defect Removal

The removal of weld metal or portions of the base metal shall be done preferably by chipping, grinding, sawing, machining, or other mechanical means. Defects also may be removed by thermal cutting techniques. If thermal cutting techniques are used, the cut surfaces shall be cleaned and smoothed by mechanical means. In addition, at least 1/8-inch of metal shall be removed by mechanical means from the cut surfaces of stainless steel.

### 3.1.5.3 Rewelding

Repair welds shall be made using an electrode or filler wire preferably smaller than that used in making the original weld. Rewelding shall be done using qualified welding procedures. The surface shall be cleaned before rewelding. Repair welds shall meet the requirements of this specification.

# 3.1.5.4 Peening or Caulking

The use of force (peening) or foreign materials to mask, fill in, seal, or disguise any welding defects shall not be permitted.

#### 3.2 INSTALLATION

### 3.2.1 Precautions

Special care shall be taken by the Contractor to insure that the protective coating on buried pipe is not damaged during installation and that the completed system is free of rocks, sand, dirt, and foreign objects. The Contractor shall take the following steps to insure these conditions.

- a. Coated pipe shall be handled only with canvas or nylon slings or padded clamps. Any coating damaged by improper handling or storage shall be repaired as specified.
- b. Pipe brought to the site shall be stored on blocks or horses at least 18 inches above the ground. Padded blocks or horses shall be used for coated pipe. The method and height of storing coated pipe shall be in accordance with the coating manufacturer's instructions.
- c. Visual inspection shall be made of the inside of each length of pipe to ensure that it is clear and clean prior to installation.
- d. The open ends of the pipe system shall be closed at the end of each day's work or when work is not in progress and shall not be opened until the work is resumed.
- e. A swab, with a leather or canvas belt disc to fit the inside

diameter of pipe, shall be pulled through each length of pipe after welding in place.

f. Obstruction remaining in the pipe after completion of the system shall be removed at the expense of the Contractor.

# 3.2.2 Protective Coatings

### 3.2.2.1 Application of Tape Wrapping

Surfaces to receive tape shall be clean, dry, grease-free and dust-free. Extruded polyethylene coating and adhesive undercoat surfaces to be tape wrapped shall be primed with a compatible primer prior to application of the tape. The primer shall be as recommended by the tape manufacturer and approved by the extruded polyethylene coating manufacturer. Weld beads shall be wire brushed. Burrs and weld spatter shall be removed. Weld beads shall be covered with one wrap of tape prior to spiral wrapping. Fittings shall be wrapped spirally beginning with one complete wrap three inches back from each edge of the extruded polyethylene coating. For pipe less than four-inch size, one layer half-lapped shall be used. For pipe four-inch size and larger, two layers half-lapped shall be used, with the second layer wrapped opposite hand to the first. On irregular surfaces one layer shall be applied half-lapped and stretched to conform to the surface, followed by a second layer half-lapped and applied with the tension as it comes off the roll.

# 3.2.2.2 Inspection and Testing

The condition of factory field coated and wrapped piping shall be the responsibility of the Contractor and all damage to the protective covering during transit and handling shall be repaired by the Contractor at no additional cost to the Government. All field coating and wrapping shall be subject to approval by the Contracting Officer. The entire pipe shall be inspected as specified in sub-paragraph "Testing of Protective Coatings" under paragraph "Protective Coatings for Buried Carbon Steel and Stainless Steel Piping." The inspection for holidays shall be performed just prior to lowering the pipe into the ditch and every precaution shall be taken during lowering and backfilling to prevent damage to the protective covering.

### 3.2.2.3 Damage Repair

Damaged areas of extruded polyethylene coating shall be repaired by tape wrapping as specified in the preceding paragraph for fittings. Residual material from the extruded polyethylene coating shall be pressed into the break or shall be trimmed off; all areas to be taped shall be primed, and the tape shall be applied half-lapped.

#### 3.3 INTERIOR EPOXY COATING

When internally epoxy lined pipe is cut, the lining shall be ground back from the end a minimum of one inch but not more than one and one-half inches.

# 3.4 VERIFICATION OF DIMENSIONS

The Contractor shall become familiar with details of the work, shall verify dimensions in the field, and shall advise the Contracting Officer of any discrepancy before performing any work.

### 3.5 CLEANING OF PIPING

The Contractor shall keep the interior and ends of all new piping affected by the Contractor's operations thoroughly cleaned of foreign matter and water before and after being installed. Piping systems shall be kept clean during installation by means of plugs or other approved methods. When work is not in progress, open ends of piping and fittings shall be closed so that no water or other foreign substance will enter the pipes or fittings. Piping shall be inspected before placing into position. The interior of each length of pipe shall be cleaned after welding. It shall be the Contractor's responsibility for insuring that the interior of the piping is free of foreign matter when it is connected into the system.

### 3.6 TRENCHING AND BACKFILLING

Trenching and backfilling shall conform to Section 02316 EXCAVATION, TRENCHING, AND BACKFILLING FOR UTILITIES SYSTEMS, and the following bedding and backfill requirements. The pipe shall be laid in a bed of sand six inches deep, compacted to the elevation of the bottom of the pipe. The full length of each section of pipe without any protective covering shall be excavated to permit installation of the protective covering. Pipe that has the grade or joint disturbed after laying, shall be taken up and relaid. Pipe shall not be laid in water or when the trench or weather conditions are unsuitable for such work. After testing and application of protective covering to joints, sand backfill shall be placed and compacted around the pipe or protective coating. The remainder of the backfill shall be the same as for other types of pipe.

#### 3.7 INSTALLATION OF UNDERGROUND PIPE

Underground fuel pipelines shall be pitched as shown on the drawings. Where not indicated they shall be pitched a minimum of 2 inches per 100 feet. Branch lines to the hydrant pits shall slope up to the pit. Vent and drain lines shall terminate in male cam-type locking end dry breaks with matching female dust covers and installed in pits. The pipe shall have cover as shown on the drawings. Drain lines shall be installed at the slopes indicated.

# 3.7.1 Pipe Assembly

Pipe shall be strung parallel and adjacent to or above a trench. The pipe shall be supported on padded skids during welding and inspection of joints. Protective coating shall be inspected and repaired prior to lowering the pipe into the trench. The pipe shall be lowered using only canvas or nylon slings. The sling shall be dug from underneath the pipe after placements and shall not be pulled from underneath the pipe while in contact with it. Care shall be taken to prevent damage to the pipe, welded joints or coating and any such damage shall be repaired as directed by the Contracting Officer. Pressure testing of the pipe shall be done after it has been placed in final position in the trench.

### 3.7.2 Warning Tapes in Earth Trenches

For the purpose of early warning and identification of buried pipes outside of building walls during future trenching or other excavation, continuous identification tapes shall be provided in the trench. Tape shall be nonmagnetic plastic tape or aluminum foil plastic backed tape manufactured for the purpose of early warning and identification of utilities buried

below the tape. Tape shall be at least three inches in width. Color of tape shall be as standard with the manufacturer with respect to the type of utility buried below the tape. Tape shall have lettering at least one inch high with not less than the following identification on the tape: BURIED JET FUEL PIPING BELOW. Tape shall be installed in accordance with the printed recommendations of the tape manufacturer, as modified herein. Tapes shall be buried at a depth of six inches from the top of the subgrade.

#### 3.7.3 Clearances

Install pipe to be clear of contact with other pipes, pipe sleeves, casings, reinforcing steel, conduits, cables, or other metallic structures. Where pipes cross other pipes or structures with a separation of less than six inches, install an insulating separator. Protect the pipe from contact with a 12-inch square by 1 inch thick bituminous-impregnated canefiber board.

#### 3.7.4 Protective Coating

When the protective coating on pipe is damaged, the Contracting Officer shall be notified and shall inspect the pipe before the coating is patched. If the damage to the pipe is deeper than 0.050-inch, the damage shall be repaired by welding in accordance with paragraph "WELDING". If the pipe is dented, out of round or damaged to the point that welding will not make it good as new, the length of pipe shall be rejected.

### 3.8 PIPING LAYOUT REQUIREMENTS

#### 3.8.1 Pipe Fabrication

Fabricate piping to measurements established on the project site and position into place without springing or forcing. Make provisions for absorbing expansion and contraction without undue stress in any part of the system.

#### 3.8.2 Interferences and Measurements

Provide offsets, fittings, and accessories required to eliminate interferences and to match actual equipment connection locations and arrangements. Verify measurements before commencing work. Submit discrepancies for clarification before proceeding with the installations to the Contracting Officer.

# 3.8.3 Space and Access

Keep piping, control tubing, which is not detailed close to structures and columns so as to take up a minimum amount of space. Ensure that access is provided for maintenance of equipment, valves and gauges.

#### 3.8.4 Location

Do not place unions in locations that will be inaccessible after the completion of the work. Place unions on each side of equipment.

### 3.8.5 Piping and Equipment

Provide anchors where required to absorb or transmit thrust or eliminate vibration or pulsation. Provide hangers and supports near each change of direction. Select support components which do not restrict the movement of

the pipe due to thermal expansion. Space hangers uniformly and arrange symmetrically.

# 3.8.6 Structural Support

Provide supplementary or intermediate steel or other structural members as required for transmission of loads to members forming part of the supporting structure.

### 3.8.7 Grade

Where profiles of piping lines are shown on the drawings, grade the line uniformly between changes in slope or direction. Maintain gradient to within  $\pm$  1/4-inch over the entire length of pipe. When backfilling has been completed to the top of the pipe, the pipe shall be surveyed at each joint, logged by station number, and submitted to the Contracting Officer and approved before backfilling can continue.

# 3.8.8 Size Changes

Make changes in pipe size with reducing fittings. Do not use bushings. In lieu of welding reducing outlet tees for piping 2 inches and larger, welding branches suitable for 100 percent radiographic inspection may be used. Do not use weldolets unless specifically called out (labeled) on the drawings.

## 3.8.9 Direction Changes

Make changes in the horizontal direction of pipes with long radius fittings. Provide special fittings when required. Do not make miter welds. Make odd-angle offsets with pipe bends or elbows cut to the proper angle.

#### 3.9 TESTING

Piping shall be tested by pneumatic and hydrostatic pressure. Testing shall comply with applicable requirements of ASME B31.3, NFPA 30 and the requirements specified herein. Hydrostatic testing shall be performed using fuel as the liquid. Water shall not be introduced into the system for testing. Pressure and hydrostatic testing shall be performed only after welding inspection has been completed.

#### 3.9.1 General

Piping to be installed underground shall not receive field applied protective covering at the joints or be covered by backfill until the piping has passed the pneumatic test described herein. To facilitate the tests, the Contractor shall isolate various sections of the piping system and test each one separately. Where such sections terminate at flanged valve points, the line shall be closed by means of blind flanges in lieu of relying on the valve. The Contractor shall furnish tapped flanges that can be attached to the end of the section of line being tested, and that will permit a direct connection between the piping and the air compressor and/or pressurizing pump. No taps in the permanent line will be permitted. The Contractor shall furnish all necessary equipment for testing; all gauges shall be subject to testing and approval of the Contracting Officer. The air used for pneumatic testing shall have a residual humidity of not over 20 percent. The Contractor shall provide dehumidifying equipment on the suction or discharge side of the air compressor used to provide air for

testing. Pressurizing pump shall not exceed 10 cfm.

#### 3.9.1.1 Pneumatic Test Procedure

Special safety measures, including the wearing of face mask, shall be taken during testing under pressure. Only authorized personnel shall be permitted in the area during testing. The pneumatic test pressure shall be applied in increments. A preliminary 25 psig test shall be applied. Examine joints with soap solution. Leaks revealed by this test shall be repaired. The full test pressure shall then be applied. Unless otherwise directed by the Contracting Officer, all piping shall be tested at a pressure of 50 psig for not less than 2 hours, during which time there shall be no drop in pressure, only pressure rises with temperature. The pressure source shall be disconnected during the final test period. Any leaks revealed by the test shall be repaired and the test repeated.

#### 3.9.1.2 Hydrostatic Test Procedure

Upon completion of pneumatic testing and after backfilling, hydrostatically test each piping system with fuel at 275 psig in accordance with ASME B31.3 and API RP 1110, with no leakage or reduction in gauge pressure for four hours. The Contractor shall furnish electricity, instruments, connecting devices, and personnel for test. Fuel shall be furnished by the Government. Defects in work provided by the Contractor shall be corrected by him at his own expense, and the test repeated until the work is proven to be in compliance with the Contract requirements.

### 3.9.2 Performance Testing

The completed fuel system shall be cleaned and performance tested as specified in Section 15899 SYSTEM START UP, FUELING SYSTEM. All control valves, both manual and automatic, shall be checked for leaks (any area wetted with fuel) and proper operation and adjusted, repaired or replaced to correct any defects.

-- End of Section --

# SECTION 16415

# ELECTRICAL WORK, INTERIOR

# PART 1 GENERAL

### 1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

# AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI C39.1	(1981; R 1992) Requirements for Electrical Analog Indicating Instruments
ANSI C78.1	(1991; C78.1a; R 1996) Fluorescent Lamps - Rapid-Start Types - Dimensional and Electrical Characteristics
ANSI C82.1	(1997) Specifications for Fluorescent Lamp Ballasts $\$18.00\$\F\X$ Addenda D & E
ANSI C82.4	(1992) Ballasts for High-Intensity-Discharge and Low-Pressure Sodium Lamps (Multiple-Supply Type)
AMERICAN SOCIETY FOR TES	STING AND MATERIALS (ASTM)
ASTM B 1	(1995) Hard-Drawn Copper Wire

ASTM B	1	(1995) Hard-Drawn Copper Wire
ASTM B	8	(1999) Concentric-Lay-Stranded Copper Conductors, Hard, Medium-Hard, or Soft
ASTM D	709	(2000) Laminated Thermosetting Materials
	INSTITUTE OF ELECTRICAL	AND ELECTRONICS ENGINEERS (IEEE)

I	EEE C6	2.41	(1991; R 1995) Surge Voltages in Low-Voltage AC Power Circuits
I	EEE Sto	d 242	(1986; R 1991) Recommended Practice for Protection and Coordination of Industrial and Commercial Power Systems
I	EEE Sto	d 399	(1997) Recommended Practice for Industrial and Commercial Power Systems Analysis
I	EEE Sto	d 81	(1983) Guide for Measuring Earth

(1983) Guide for Measuring Earth
Resistivity, Ground Impedance, and Earth
Surface Potentials of a Ground System
(Part 1) \\$31.00\$\F

# NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA 250	(1997) Enclosures for Electrical Equipment (1000 Volts Maximum)	
NEMA AB 1	(1993) Molded Case Circuit Breakers and Molded Case Switches	
NEMA FU 1	(1986) Low Voltage Cartridge Fuses	
NEMA ICS 1	(1993) Industrial Control and Systems	
NEMA ICS 2	(1993) Industrial Controls and Systems Controllers, Contactors, and Overload Relays Rated Not More Than 2,000 Volts AC or 750 Volts DC	
NEMA ICS 3	(1993) Industrial Control and Systems Factory Built Assemblies	
NEMA ICS 6	(1993) Enclosures for Industrial Control and Systems	
NEMA LE 4	(1987) Recessed Luminaires, Ceiling Compatibility	
NEMA MG 1	(1998) Motors and Generators	
NEMA MG 10	(1994) Energy Management Guide for Selection and Use of Polyphase Motors	
NEMA OS 1	(1996) Sheet-Steel Outlet Boxes, Device Boxes, Covers, and Box Supports	
NEMA RN 1	(1998) Polyvinyl-Chloride (PVC) Externally Coated Galvanized Rigid Steel Conduit and Intermediate Metal Conduit	
NEMA WD 1	(1999) General Requirements for Wiring Devices	
NEMA WD 6	(1997) Wiring Devices - Dimensional Requirements	
NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)		
NFPA 101	(2000) Life Safety Code	
NFPA 70	(2002) National Electrical Code	
U.S. NATIONAL ARCHIVES	AND RECORDS ADMINISTRATION (NARA)	
47 CFR 18	Industrial, Scientific, and Medical Equipment	
UNDERWRITERS LABORATORI	TES (UL)	
UL 1	(2000) Flexible Metal Conduit	
UL 1004	(1994; Rev thru Nov 1999) Electric Motors	

UL 1029	(1994; Rev thru Dec 1997) High-Intensity-Discharge Lamp Ballasts
UL 1242	(1996; Rev Mar 1998) Intermediate Metal Conduit
UL 1570	(1995; Rev thru Nov 1999) Fluorescent Lighting Fixtures
UL 1572	(1995; Rev thru Nov 1999) High Intensity Discharge Lighting Fixtures
UL 198C	(1986; Rev thru Feb 1998) High-Interrupting-Capacity Fuses, Current-Limiting Types
UL 198D	(1995) Class K Fuses
UL 198E	(1988; Rev Jul 1988) Class R Fuses
UL 198G	(1988; Rev May 1988) Fuses for Supplementary Overcurrent Protection
UL 198L	(1995; Rev May 1995) D-C Fuses for Industrial Use
UL 20	(1995; Rev thru Oct 1998) General-Use Snap Switches
UL 360	(1996; Rev thru Oct 1997) Liquid-Tight Flexible Steel Conduit
UL 467	(1993; Rev thru Apr 1999) Grounding and Bonding Equipment
UL 486A	(1997; Rev thru Dec 1998) Wire Connectors and Soldering Lugs for Use with Copper Conductors
UL 486C	(1997; Rev thru Aug 1998) Splicing Wire Connectors
UL 486E	(1994; Rev thru Feb 1997) Equipment Wiring Terminals for Use with Aluminum and/or Copper Conductors
UL 489	(1996; Rev thru Dec 1998) Molded-Case Circuit Breakers, Molded-Case Switches, and Circuit-Breaker Enclosures
UL 498	(1996; Rev thru Jan 1999) Attachment Plugs and Receptacles
UL 50	(1995; Rev thru Nov 1999) Enclosures for Electrical Equipment
UL 508	(1999) Industrial Control Equipment
UL 510	(1994; Rev thru Apr 1998) Polyvinyl

	Chloride, Polyethylene, and Rubber Insulating Tape
UL 512	(1993; Rev thru Mar 1999) Fuseholders
UL 514A	(1996; Rev Dec 1999) Metallic Outlet Boxes
UL 514B	(1997; Rev Oct 1998) Fittings for Cable and Conduit
UL 542	(1999) Lampholders, Starters, and Starter Holders for Fluorescent Lamps
UL 6	(1997) Rigid Metal Conduit
UL 674	(1994; Rev thru Oct 1998) Electric Motors and Generators for Use in Division 1 Hazardous (Classified) Locations
UL 698	(1995; Rev thru Mar 1999) Industrial Control Equipment for Use in Hazardous (Classified) Locations
UL 797	(1993; Rev thru Mar 1997) Electrical Metallic Tubing
UL 83	(1998; Rev thru Sep 1999) Thermoplastic-Insulated Wires and Cables
UL 844	(1995; Rev thru Mar 1999) Electric Lighting Fixtures for Use in Hazardous (Classified) Locations
UL 845	(1995; Rev thru Nov 1999) Motor Control Centers
UL 886	(1994; Rev thru Apr 1999) Outlet Boxes and Fittings for Use in Hazardous (Classified) Locations
UL 943	(1993; Rev thru May 1998) Ground-Fault Circuit-Interrupters
UL 98	(1994; Rev thru Jun 1998) Enclosed and Dead-Front Switches

# 1.2 GENERAL

# 1.2.1 Rules

The installation shall conform to the requirements of NFPA 70 and NFPA 101, unless more stringent requirements are indicated or shown.

# 1.2.2 Coordination

The drawings indicate the extent and the general location and arrangement of equipment, conduit, and wiring. The Contractor shall become familiar with all details of the work and verify all dimensions in the field so that

the outlets and equipment shall be properly located and readily accessible. Lighting fixtures, outlets, and other equipment and materials shall be carefully coordinated with mechanical or structural features prior to installation and positioned according to architectural reflected ceiling plans; otherwise, lighting fixtures shall be symmetrically located according to the room arrangement when uniform illumination is required, or asymmetrically located to suit conditions fixed by design and shown. Raceways, junction and outlet boxes, and lighting fixtures shall not be supported from sheet metal roof decks. If any conflicts occur necessitating departures from the drawings, details of and reasons for departures shall be submitted and approved prior to implementing any change. The Contractor shall coordinate the electrical requirements of the mechanical work and provide all power related circuits, wiring, hardware and structural support, even if not shown on the drawings.

### 1.2.3 Special Environments

#### 1.2.3.1 Weatherproof Locations

Wiring, Fixtures, and equipment in designated locations shall conform to NFPA 70 requirements for installation in damp or wet locations.

#### 1.2.3.2 Hazardous Locations

Wiring and equipment in locations indicated shall be of the classes, groups, divisions, and suitable for the operating temperature; as indicated.

### 1.2.3.3 Ducts, Plenums and Other Air-Handling Spaces

Wiring and equipment in ducts, plenums and other air-handling spaces shall be installed using materials and methods in conformance with NFPA 70 unless more stringent requirements are indicated in this specification or on the contract drawings.

### 1.2.4 Standard Products

Material and equipment shall be a standard product of a manufacturer regularly engaged in the manufacture of the product and shall essentially duplicate items that have been in satisfactory use for at least 2 years prior to bid opening.

# 1.2.5 Nameplates

# 1.2.5.1 Identification Nameplates

Major items of electrical equipment and major components shall be permanently marked with an identification name to identify the equipment by type or function and specific unit number as indicated. Designation of motors shall coincide with their designation in the motor control center or panel. Unless otherwise specified, identification nameplates shall be made of laminated plastic in accordance with ASTM D 709 with black outer layers and a white core. Edges shall be chamfered. Plates shall be fastened with black-finished round-head drive screws, except motors, or approved nonadhesive metal fasteners. When the nameplate is to be installed on an irregular-shaped object, the Contractor shall devise an approved support suitable for the application and ensure the proper installation of the supports and nameplates. In all instances, the nameplate shall be installed in a conspicuous location. The front of each panelboard, motor control center, switchgear, and switchboard shall have a nameplate to

indicate the phase letter, corresponding color and arrangement of the phase conductors. The following equipment, as a minimum, shall be provided with identification nameplates:

Minimum 1/4 inch High Letters Minimum 1/8 inch High Letters

Control Power Transformers

Starters
Safety Switches
Motor Control Centers
Equipment Enclosures
Motors

Control Devices
Instrument Transformers

Each panel, section, or unit in motor control centers or similar assemblies shall be provided with a nameplate in addition to nameplates listed above, which shall be provided for individual compartments in the respective assembly, including nameplates which identify "future," "spare," and "dedicated" or "equipped spaces."

### 1.2.6 As-Built Drawings

Following the project completion or turnover, within 30 days the Contractor shall furnish 2 sets of as-built drawings to the Contracting Officer.

#### 1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Interior Electrical Equipment; G-AE

Detail drawings consisting of equipment drawings, illustrations, schedules, instructions, diagrams, and other information necessary to define the installation. Detail drawings shall show the rating of items and systems and how the components of an item and system are assembled, function together, and how they will be installed on the project. Data and drawings for component parts of an item or system shall be coordinated and submitted as a unit. Data and drawings shall be coordinated and included in a single submission. Multiple submissions for the same equipment or system are not acceptable except where prior approval has been obtained from the Contracting Officer. In such cases, a list of data to be submitted later shall be included with the first submission. Detail drawings shall show physical arrangement, construction details, connections, finishes, materials used in fabrication, provisions for conduit or busway entrance, access requirements for installation and maintenance, physical size, electrical characteristics, foundation and support details, and equipment weight. Drawings shall be drawn to scale and/or dimensioned. Optional items shall be clearly identified as included or excluded. Detail drawings shall as a minimum include:

a. Motors and rotating machinery.

- b. Motor control centers.
- c. Single line electrical diagrams including primary, metering, control wiring, and control logic.
  - d. Sway bracing for suspended luminaires.

Structural drawings showing the structural or physical features of major equipment items, components, assemblies, and structures, including foundations or other types of supports for equipment and conductors. These drawings shall include accurately scaled or dimensioned outline and arrangement or layout drawings to show the physical size of equipment and components and the relative arrangement and physical connection of related components. Weights of equipment, components and assemblies shall be provided when required to verify the adequacy of design and proposed construction of foundations or other types of supports. Dynamic forces shall be stated for switching devices when such forces must be considered in the design of support structures. The appropriate detail drawings shall show the provisions for leveling, anchoring, and connecting all items during installation, and shall include any recommendations made by the manufacturer.

Electrical drawings including single-line and three-line diagrams, and schematics or elementary diagrams of each electrical system; internal wiring and field connection diagrams of each electrical device when published by the manufacturer; wiring diagrams of cabinets, panels, units, or separate mountings; interconnection diagrams that show the wiring between separate components of assemblies; field connection diagrams that show the termination of wiring routed between separate items of equipment; internal wiring diagrams of equipment showing wiring as actually provided for this project. Field wiring connections shall be clearly identified.

If departures from the contract drawings are deemed necessary by the Contractor, complete details of such departures, including changes in related portions of the project and the reasons why, shall be submitted with the detail drawings. Approved departures shall be made at no additional cost to the Government.

### SD-03 Product Data

Fault Current and Protective Device Coordination Study; G-AE

Manufacturer's Catalog; G-AO

Material, Equipment, and Fixture Lists.

## As-Built Drawings; G-AO

The as-built drawings shall be a record of the construction as installed. The drawings shall include all the information shown on the contract drawings, deviations, modifications, and changes from the contract drawings, however minor. The as-built drawings shall be kept at the job site and updated daily. The as-built drawings shall be a full-sized set of prints marked to reflect all deviations, changes, and modifications. The as-built drawings

shall be complete and show the location, size, dimensions, part identification, and other information. Additional sheets may be added. The as-built drawings shall be jointly inspected for accuracy and completeness by the Contractor's quality control representative and by the Contracting Officer prior to the submission of each monthly pay estimate. Upon completion of the work, the Contractor shall submit three full sized sets of the marked prints to the Contracting Officer for approval. If upon review, the as-built drawings are found to contain errors and/or omissions, they will be returned to the Contractor for correction. The Contractor shall correct and return the as-built drawings to the Contracting Officer for approval within ten calendar days from the time the drawings are returned to the Contractor.

## SD-06 Test Reports

Factory Test Reports; G-AO

Field Test Plan; G-AE

Field Test Reports; G-AO

Six copies of the information described below in  $8\ 1/2\ x\ 11$  inch binders having a minimum of 5 rings from which material may readily be removed and replaced, including a separate section for each test. Sections shall be separated by heavy plastic dividers with tabs.

- a. A list of equipment used, with calibration certifications.
- b. A copy of measurements taken.
- c. The dates of testing.
- d. The equipment and values to be verified.
- e. The conditions specified for the test.
- f. The test results, signed and dated.
- g. A description of adjustments made.
- h. Final position of controls and device settings.

## SD-07 Certificates

Materials and Equipment; G-AO

The label or listing of the Underwriters Laboratories, Inc., will be accepted as evidence that the materials or equipment conform to the applicable standards of that agency. In lieu of this label or listing, a statement from a nationally recognized, adequately equipped testing agency indicating that the items have been tested in accordance with required procedures and that the materials and equipment comply with all contract requirements will be accepted. However, materials and equipment installed in hazardous locations must bear the UL label unless the data submitted from other testing agency is specifically approved in writing by the Contracting Officer. Items which are required to

be listed and labeled in accordance with Underwriters Laboratories must be affixed with a UL label that states that it is UL listed. No exceptions or waivers will be granted to this requirement. Materials and equipment will be approved based on the manufacturer's published data.

For other than equipment and materials specified to conform to UL publications, a manufacturer's statement indicating complete compliance with the applicable standard of the American Society for Testing and Materials, National Electrical Manufacturers Association, or other commercial standard, is acceptable.

### 1.4 WORKMANSHIP

Materials and equipment shall be installed in accordance with NFPA 70, recommendations of the manufacturer, and as shown.

### 1.5 SEISMIC REQUIREMENTS

Seismic details shall conform to Sections 13080 SEISMIC PROTECTION FOR MISCELLANEOUS EQUIPMENT and 16070 SEISMIC PROTECTION FOR ELECTRICAL EQUIPMENT.

### 1.6 INTERIOR ELECTRICAL EQUIPMENT

Detail drawings consisting of equipment drawings, illustrations, schedules, instructions, diagrams, and other information necessary to define the installation. Detail drawings shall show the rating of items and systems and how the components of an item and system are assembled, function together, and how they will be installed on the project. Data and drawings for component parts of an item or system shall be coordinated and submitted as a unit. Data and drawings shall be coordinated and included in a single submission. Multiple submissions for the same equipment or system are not acceptable except where prior approval has been obtained from the Contracting Officer. In such cases, a list of data to be submitted later shall be included with the first submission. Detail drawings shall show physical arrangement, construction details, connections, finishes, materials used in fabrication, provisions for conduit or busway entrance, access requirements for installation and maintenance, physical size, electrical characteristics, foundation and support details, and equipment weight. Drawings shall be drawn to scale and/or dimensioned. Optional items shall be clearly identified as included or excluded. Detail drawings shall as a minimum include:

- a. Motors and rotating machinery.
- b. Motor control centers.
- c. Single line electrical diagrams including primary, metering, control wiring, and control logic.
- d. Sway bracing for suspended luminaires.

Structural drawings showing the structural or physical features of major equipment items, components, assemblies, and structures, including foundations or other types of supports for equipment and conductors. These drawings shall include accurately scaled or dimensioned outline and arrangement or layout drawings to show the physical size of equipment and components and the relative

arrangement and physical connection of related components. Weights of equipment, components and assemblies shall be provided when required to verify the adequacy of design and proposed construction of foundations or other types of supports. Dynamic forces shall be stated for switching devices when such forces must be considered in the design of support structures. The appropriate detail drawings shall show the provisions for leveling, anchoring, and connecting all items during installation, and shall include any recommendations made by the manufacturer.

Electrical drawings including single-line and three-line diagrams, and schematics or elementary diagrams of each electrical system; internal wiring and field connection diagrams of each electrical device when published by the manufacturer; wiring diagrams of cabinets, panels, units, or separate mountings; interconnection diagrams that show the wiring between separate components of assemblies; field connection diagrams that show the termination of wiring routed between separate items of equipment; internal wiring diagrams of equipment showing wiring as actually provided for this project. Field wiring connections shall be clearly identified.

If departures from the contract drawings are deemed necessary by the Contractor, complete details of such departures, including changes in related portions of the project and the reasons why, shall be submitted with the detail drawings. Approved departures shall be made at no additional cost to the Government.

### 1.7 FAULT CURRENT AND PROTECTIVE DEVICE COORDINATION STUDY

The study shall be submitted along with protective device equipment submittals. No time extensions or similar contract modifications will be granted for work arising out of the requirements for this study. Approval of protective devices proposed shall be based on recommendations of this study, The Government shall not be held responsible for any changes to equipment, device ratings, settings, or additional labor for installation of equipment or devices ordered and/or procured prior to approval of the study.

## 1.8 MANUFACTURER'S CATALOG

Data composed of catalog cuts, brochures, circulars, specifications, product data, and printed information in sufficient detail and scope to verify compliance with the requirements of the contract documents.

## 1.9 MATERIAL, EQUIPMENT, AND FIXTURE LISTS

A complete itemized listing of equipment and materials proposed for incorporation into the work. Each entry shall include an item number, the quantity of items proposed, and the name of the manufacturer of each item.

## 1.10 FACTORY TEST REPORTS

Six copies of the information described below in  $8\ 1/2\ x\ 11$  inch binders having a minimum of 5 rings from which material may readily be removed and replaced, including a separate section for each test. Sections shall be separated by heavy plastic dividers with tabs.

a. A list of equipment used, with calibration certifications.

- b. A copy of measurements taken.
- c. The dates of testing.
- d. The equipment and values to be verified.
- e. The conditions specified for the test.
- f. The test results, signed and dated.
- g. A description of adjustments made.

### 1.11 FIELD TEST PLAN

A detailed description of the Contractor's proposed procedures for onsite test submitted 30 days prior to testing the installed system. No field test will be performed until the test plan is approved. The test plan shall consist of complete field test procedures including tests to be performed, test equipment required, and tolerance limits.

### PART 2 PRODUCTS

Products shall conform to the respective publications and other requirements specified below. Materials and equipment not listed below shall be as specified elsewhere in this section. Items of the same classification shall be identical including equipment, assemblies, parts, and components.

### 2.1 CABLES AND WIRES

Conductors No. 8 AWG and larger diameter shall be stranded. Conductors No. 10 AWG and smaller diameter shall be solid, except that conductors for remote control, alarm, and signal circuits, classes 1, 2, and 3, shall be stranded unless specifically indicated otherwise. Conductor sizes and ampacities shown are based on copper, unless indicated otherwise. All conductors shall be copper.

## 2.1.1 Equipment Manufacturer Requirements

When manufacturer's equipment requires copper conductors at the terminations or requires copper conductors to be provided between components of equipment, provide copper conductors or splices, splice boxes, and other work required to meet manufacturer's requirements.

### 2.1.2 Aluminum Conductors

Aluminum conductors shall not be used.

### 2.1.3 Insulation

Unless indicated otherwise, or required by NFPA 70, power and lighting wires shall be 600-volt, Type THWN/ THHN conforming to UL 83, except that grounding wire may be type TW conforming to UL 83; remote-control and signal circuits shall be Type TW, THW or TF, conforming to UL 83. Where lighting fixtures require 90-degree Centigrade (C) conductors, provide only conductors with 90-degree C insulation or better.

### 2.1.4 Bonding Conductors

ASTM B 1, solid bare copper wire for sizes No. 8 AWG and smaller diameter; ASTM B 8, Class B, stranded bare copper wire for sizes No. 6 AWG and larger diameter.

### 2.2 CIRCUIT BREAKERS

### 2.2.1 MOLDED-CASE CIRCUIT BREAKERS

Molded-case circuit breakers shall conform to NEMA AB 1 and UL 489. Circuit breakers may be installed in panelboards, switchboards, motor control centers, or combination motor controllers.

### 2.2.1.1 Construction

Circuit breakers shall be suitable for mounting and operating in any position. Lug shall be listed for copper conductors in accordance with UL 486E. Single-pole circuit breakers shall be full module size with not more than one pole per module. Multi-pole circuit breakers shall be of the common-trip type having a single operating handle such that an overload or short circuit on any one pole will result in all poles opening simultaneously. Sizes of 100 amperes or less may consist of single-pole breakers permanently factory assembled into a multi-pole unit having an internal, mechanical, nontamperable common-trip mechanism and external handle ties. All circuit breakers shall have a quick-make, quick-break overcenter toggle-type mechanism, and the handle mechanism shall be trip-free to prevent holding the contacts closed against a short-circuit or sustained overload. All circuit breaker handles shall assume a position between "ON" and "OFF" when tripped automatically. All ratings shall be clearly visible.

## 2.2.1.2 Ratings

Voltage ratings shall be not less than the applicable circuit voltage. The interrupting rating of the circuit breakers shall be at least equal to the available short-circuit current at the line terminals of the circuit breaker and correspond to the UL listed integrated short-circuit current rating specified for the panelboards and switchboards. Molded-case circuit breakers shall have nominal voltage ratings, maximum continuous-current ratings, and maximum short-circuit interrupting ratings in accordance with NEMA AB 1. Series rated breakers are not acceptable.

## 2.2.1.3 Thermal-Magnetic Trip Elements

Thermal magnetic circuit breakers shall be provided as shown. Automatic operation shall be obtained by means of thermal-magnetic tripping devices located in each pole providing inverse time delay and instantaneous circuit protection.

### 2.3 CONDUIT AND TUBING

2.3.1 Electrical, Zinc-Coated Steel Metallic Tubing (EMT)

UL 797

## 2.3.2 Flexible Conduit, Steel

General-purpose type, UL 1; liquid tight, UL 360.

2.3.3 Intermediate Metal Conduit

UL 1242.

2.3.4 PVC Coated Rigid Steel Conduit

NEMA RN 1.

2.3.5 Rigid Metal Conduit

UL 6.

2.4 CONDUIT AND DEVICE BOXES AND FITTINGS

Set-screw fittings for use with EMT conduits shall not be permitted. Flexible metal conduit shall use compression type fittings and no couplings.

2.4.1 Boxes, Metallic Outlet

NEMA OS 1 and UL 514A.

- 2.4.2 Boxes, Outlet for Use in Hazardous (Classified) Locations UL 886.
- 2.4.3 Boxes, Switch (Enclosed), Surface-Mounted UL 98.
- 2.4.4 Fittings for Conduit and Outlet Boxes
  UL 514B.
- 2.4.5 Fittings For Use in Hazardous (Classified) Locations UL 886.
- 2.5 CONDUIT COATINGS PLASTIC RESIN SYSTEM

NEMA RN 1, Type A-40.

- 2.6 CONNECTORS, WIRE PRESSURE
- 2.6.1 For Use With Copper Conductors
  UL 486A.
- 2.7 ELECTRICAL GROUNDING AND BONDING EQUIPMENT

UL 467.

2.7.1 Ground Rods

Ground rods shall be of copper-clad steel conforming to UL 467 not less than 3/4 inch in diameter by 10 feet in length driven full length into the earth.

2.8 ENCLOSURES

NEMA ICS 6 or NEMA 250 or UL 698 for use in hazardous (classified) locations, unless otherwise specified.

## 2.8.1 Cabinets and Boxes

Cabinets and boxes with volume greater than 100 cubic inches shall be in accordance with UL 50, hot-dip, zinc-coated, if sheet steel.

2.9 LIGHTING FIXTURES, LAMPS, BALLASTS, EMERGENCY EQUIPMENT, CONTROLS AND ACCESSORIES

The following specifications are supported and supplemented by information and details on the drawings. Additional fixtures, if shown, shall conform to this specification. Lighting equipment installed in classified hazardous locations shall conform to UL 844. Lamps, lampholders, ballasts, transformers, electronic circuitry and other lighting system components shall be constructed according to industry standards. Equipment shall be tested and listed by a recognized independent testing laboratory for the expected installation conditions. Equipment shall conform to the standards listed below.

## 2.9.1 Lamps

Lamps shall be constructed to operate in the specified fixture, and shall function without derating life or output as listed in published data. Lamps shall meet the requirements of the Energy Policy Act of 1992.

a. Fluorescent lamps shall have color temperature 3,500degrees Kelvin. They shall be designed to operate with the ballasts and circuitry of the fixtures in which they will be used. Fluorescent lamps, including spares, shall be manufactured by one manufacturer to provide for color and performance consistency. Fluorescent lamps shall comply with ANSI C78.1. Fluorescent tube lamp efficiencies shall meet or exceed the following requirements.

T8, 32 watts (4' lamp) 2800 lumens

- (1) Linear fluorescent lamps, unless otherwise indicated, shall be 4 feet long 32 watt T8, 265 mA, with minimum CRI of 75. Lamps of other lengths or types shall be used only where specified or shown. Lamps shall deliver rated life when operated on rapid start ballasts.
- b. High intensity discharge lamps, including spares, shall be manufactured by one manufacturer in order to provide color and performance consistency. High intensity discharge lamps shall be designed to operate with the ballasts and circuitry of the fixtures in which they will be used and shall have wattage, shape and base as shown. High intensity discharge lamps, unless otherwise shown, shall have medium or mogul screw base and minimum starting temperature of -20 degrees F. Metal halide lamps, unless otherwise shown, shall have minimum CRI of 65; color temperature of 4,300 degrees Kelvin; shall be -BU configuration if used in base-up position. Lamps shall comply with all applicable ANSI requirements for the watttage indicated.

## 2.9.2 Ballasts and Transformers

Ballasts or transformers shall be designed to operate the designated lamps within their optimum specifications, without derating the lamps. Lamp and ballast combinations shall be certified as acceptable by the lamp manufacturer.

- a. Fluorescent ballasts shall comply with ANSI C82.1 and shall be mounted integrally within fluorescent fixture housing unless otherwise shown. Ballasts shall have maximum current crest factor of 1.7; high power factor; Class A sound rating; maximum operating case temperature of 77 degrees F above ambient; and shall be rated Class P. Unless otherwise indicated, the minimum number of ballasts shall be used to serve each individual fixture.
  - (1) Electronic fluorescent ballasts shall comply with 47 CFR 18 for electromagnetic interference. Ballasts shall withstand line transients per IEEE C62.41, Category A. Ballasts shall have total harmonic distortion between 10 and 20%; minimum frequency of 20,000Hz; filament voltage between 2.5 and 4.5 volts; maximum starting inrush current of 20 amperes; and shall comply with the minimum Ballast Efficacy Factors shown in the table below. Minimum starting temperature shall be 50 degrees F. Ballasts shall carry a manufacturer's full warranty of three years, including a minimum \$10 labor allowance per ballast.

### ELECTRONIC FLUORESCENT BALLAST EFFICACY FACTORS

LAMP TYPE	TYPE OF STARTER & LAMP	NOMINAL OPERATIONAL VOLTAGE	NUMBER OF LAMPS	MINIMUM BALLAST EFFICACY FACTOR
32W T8	rapid start linear	120 or 277 V	1 2 3	2.54 1.44 0.93

- b. High intensity discharge ballasts shall comply with UL 1029 and, if multiple supply types, with ANSI C82.4. Ballasts shall have minimum ballast factor of 0.9; high power factor; Class A sound rating; and maximum operating case temperature of 77 degrees F above ambient.
  - (1) Electronic high intensity discharge ballasts shall be constant wattage autotransformer type; shall have less than 10% ballast loss; shall have total harmonic distortion between 10 and 20%; and shall have a minimum starting temperature of 0 degrees F.
  - (2) Magnetic high intensity discharge ballasts shall have a minimum starting temperature of -20 degrees F.

## 2.9.3 Fixtures

Fixtures shall be in accordance with the size, shape, appearance, finish, and performance shown. Unless otherwise indicated, lighting fixtures shall be provided with housings, junction boxes, wiring, lampholders, mounting supports, trim, hardware and accessories for a complete and operable installation. Recessed housings shall be minimum 20 gauge cold rolled or galvanized steel as shown. Extruded aluminum fixtures shall have minimum

wall thickness of 0.125 inches. Plastic lenses shall be 100% virgin acrylic or as shown. Glass lenses shall be tempered. Heat resistant glass shall be borosilicate type. Conoid recessed reflector cones shall be Alzak with clear specular low iridescent finish.

- a. Fluorescent fixtures shall comply with UL 1570. Recessed ceiling fixtures shall comply with NEMA LE 4. Fixtures shall be plainly marked for proper lamp and ballast type to identify lamp diameter, wattage, color and start type. Marking shall be readily visible to service personnel, but not visible from normal viewing angles. Fluorescent fixture lens frames on recessed and surface mounted troffers shall be one assembly with mitered corners. Parabolic louvers shall have a low iridescent finish and 45 degree cut-off. Louver intersection joints shall be hairline type and shall conceal mounting tabs or other assembly methods. Louvers shall be free from blemishes, lines or defects which distort the visual surface. Integral ballast and wireway compartments shall be easily accessible without the use of special tools. Housings shall be constructed to include grounding necessary to start the lamps. Medium bi-pin lampholders shall be twist-in type with positive locking position.
- . High intensity discharge fixture shall comply with UL 1572. Lampholders shall be pulse-rated to 5,000 volts. Fixtures indicated as classified or rated for hazardous locations or special service shall be designed and independently tested for the environment in which they are installed. Ballasts shall be integral to fixtures and shall be accessible without the use of special tools. Lamps shall be shielded from direct view with a UV absorbing material such as tempered glass, and shall be circuited through a cut-off switch which will shut off the lamp circuit if the lens is not in place.
- c. Emergency lighting accessories shall be constructed and independently tested to meet the requirements of applicable codes. Batteries shall be Nicad or equal with no required maintenance, and shall have a minimum life expectancy of five years and warranty period of three years.
- 2.9.4 Lampholders, Starters, and Starter Holders

UL 542

- 2.10 LOW-VOLTAGE FUSES AND FUSEHOLDERS
- 2.10.1 Fuses, Low Voltage Cartridge Type

NEMA FU 1.

- 2.10.2 Fuses, High-Interrupting-Capacity, Current-Limiting Type Fuses, Class CC shall be in accordance with UL 198C.
- 2.10.3 Fuses, Class K, High-Interrupting-Capacity Type UL 198D.
- 2.10.4 Fuses, Class R

UL 198E.

2.10.5 Fuses for Supplementary Overcurrent Protection UL 198G.

2.10.6 Fuses, D-C for Industrial Use

UL 198L.

2.10.7 Fuseholders

UL 512.

2.11 INSTRUMENTS, ELECTRICAL INDICATING

ANSI C39.1.

2.12 MOTORS, AC, FRACTIONAL AND INTEGRAL

Motors, ac, fractional and integral horsepower, 500 hp and smaller shall conform to NEMA MG 1 and UL 1004 for motors; NEMA MG 10 for energy management selection of polyphase motors; and UL 674 for use of motors in hazardous (classified) locations. In addition to the standards listed above, motors shall be provided with efficiencies as specified in the table "MINIMUM NOMINAL EFFICIENCIES" below.

## 2.12.1 Rating

The horsepower rating of motors should be limited to no more than 125 percent of the maximum load being served unless a NEMA standard size does not fall within this range. In this case, the next larger NEMA standard motor size should be used.

## 2.12.2 Motor Efficiencies

All permanently wired polyphase motors of 1 hp or more shall meet the minimum full-load efficiencies as indicated in the following table, and as specified in this specification. Motors of 1 hp or more with open, drip proof or totally enclosed fan cooled enclosures shall be high efficiency type, unless otherwise indicated. Motor efficiencies indicated in the tables apply to general-purpose, single-speed, polyphase induction motors. Applications which require definite purpose, special purpose, special frame, or special mounted polyphase induction motors are excluded from these efficiency requirements. Motors provided as an integral part of motor driven equipment are excluded from this requirement if a minimum seasonal or overall efficiency requirement is indicated for that equipment by the provisions of another section.

TOTALLY ENCLOSED FAN-COOLED MOTORS

HP	<u>1200 RPM</u>	1800 RPM	3600 RPM
1	82.5	85.5	78.5
1.5	87.5	86.5	85.5
2	88.5	86.5	86.5
3	89.5	89.5	88.5
5	89.5	89.5	89.5

7.5	91.7	91.7	91.0
10	91.7	91.7	91.7
15	92.4	92.4	91.7
20	92.4	93.0	92.4
25	93.0	93.6	93.0
30	93.6	93.6	93.0
40	94.1	94.1	93.6
50	94.1	94.5	94.1
60	94.5	95.0	94.1
75	95.0	95.4	94.5
100	95.4	95.4	95.0
125	95.4	95.4	95.4
150	95.8	95.8	95.4
200	95.8	96.2	95.8
250	95.6	96.2	95.9

### 2.13 MOTOR CONTROLS AND MOTOR CONTROL CENTERS

#### 2.13.1 General

NEMA ICS 1, NEMA ICS 2, NEMA ICS 3 and NEMA ICS 6, and UL 508 and UL 845.

### 2.13.2 Motor Starters

Combination starters shall be provided with circuit breakers.

### 2.13.2.1 Reduced-Voltage Starters

Reduced-voltage starters shall be of the single-step autotransformer type having an adjustable time interval between application of reduced and full voltages to the motors.

## 2.13.3 Thermal-Overload Protection

Each motor of 1/8 hp or larger shall be provided with thermal-overload protection. Polyphase motors shall have overload protection in each ungrounded conductor. The overload-protection device shall be provided either integral with the motor or controller. Unless otherwise specified, the protective device shall be of the manually reset type.

## 2.13.4 Automatic Control Devices

# 2.13.4.1 Pilot-Relay Control

Where the automatic-control device (such as thermostats, float or pressure switches) does not have an adequate horepower rating, a magnetic starter shall be used, with the automatic-control device actuating the pilot-control circuit.

### 2.13.4.2 Manual/Automatic Selection

- a. Where combination manual and automatic control is specified and the automatic-control device actuates the pilot control circuit of a magnetic starter, the magnetic starter shall be provided with a three-position selector switch marked MANUAL-OFF-AUTOMATIC.
- b. Connections to the selector switch shall be such that; only the normal automatic regulatory control devices will be bypassed when

the switch is in the Manual position; all safety control devices, such as low-or high-pressure cutouts, high-temperature cutouts, and motor-overload protective devices, shall be connected in the motor-control circuit in both the Manual and the Automatic positions of the selector switch. Control circuit connections to any MANUAL-OFF-AUTOMATIC switch or to more than one automatic regulatory control device shall be made in accordance with wiring diagram approved by the Contracting Officer unless such diagram is included on the drawings. All controls shall be 120 volts or less unless otherwise indicated.

#### 2.13.5 Motor Control Centers

Control centers shall conform to the requirements of NEMA ICS 1, NEMA ICS 2, NEMA ICS 3 and NEMA ICS 6, and UL 508 and UL 845. Control centers shall be indoor type and shall contain combination starters and other equipment as indicated. Control centers shall be NEMA ICS 2, Class II, Type C. Each control center shall be mounted on floor sills or mounting channels. Each circuit shall have a suitable metal or laminated plastic nameplate with white cut letters. Motor control centers shall be provided with a full-length ground bus bar.

- 2.14 RECEPTACLES
- 2.14.1 Standard Grade

UL 498.

2.14.2 Ground Fault Interrupters

UL 943, Class A.

2.14.3 NEMA Standard Receptacle Configurations

NEMA WD 6.

a. Duplex, 15-Ampere, 125 Volt

15-ampere, non-locking: NEMA type 5-15R.

2.15 SPLICE, CONDUCTOR

UL 486C.

- 2.16 POWER-SWITCHGEAR ASSEMBLIES INCLUDING SWITCHBOARDS
- 2.16.1 Circuit Breakers

Circuit breakers shall be stationarymolded-case circuit breakers.

2.17 SNAP SWITCHES

UL 20.

- 2.18 TAPES
- 2.18.1 Plastic Tape

UL 510.

## 2.18.2 Rubber Tape

UL 510.

#### 2.19 WIRING DEVICES

NEMA WD 1 for wiring devices, and NEMA WD 6 for dimensional requirements of wiring devices.

### 2.20 COORDINATED POWER SYSTEM PROTECTION

Analyses shall be prepared to demonstrate that the equipment and system constructed meet the specified requirements for equipment ratings, coordination, and protection. They shall include a load flow analysis, a fault current analysis, and protective device coordination study. The studies shall be performed by a registered professional engineer with demonstrated experience in power system coordination in the last three years. The Contractor shall provide a list of references complete with points of contact, addresses and telephone numbers. The selection of the engineer is subject to the approval of the Contracting Officer.

## 2.20.1 Scope of Analyses

The fault current analysis, and protective device coordination study shall begin at: the nearest upstream device in the existing source system and extend through the downstream devices at the load end.

### 2.20.2 Determination of Facts

The time-current characteristics, features, and nameplate data for each existing protective device shall be determined and documented. The Contractor shall coordinate with the Base for fault current availability at the site.

## 2.20.3 Single Line Diagram

A single line diagram shall be prepared to show the electrical system buses, devices, transformation points, and all sources of fault current (including generator and motor contributions). A fault-impedance diagram or a computer analysis diagram may be provided. Each bus, device or transformation point shall have a unique identifier. If a fault-impedance diagram is provide, impedance data shall be shown. Locations of switches, breakers, and circuit interrupting devices shall be shown on the diagram together with available fault data, and the device interrupting rating.

## 2.20.4 Fault Current Analysis

### 2.20.4.1 Method

The fault current analysis shall be performed in accordance with methods described in IEEE Std 242, and IEEE Std 399.

### 2.20.4.2 Data

Actual data shall be utilized in fault calculations. Bus characteristics and transformer impedances shall be those proposed. Data shall be documented in the report.

## 2.20.4.3 Fault Current Availability

Balanced three-phase fault, bolted line-to-line fault, and line-to-ground fault current values shall be provided at each voltage transformation point and at each power distribution bus. The maximum and minimum values of fault available at each location shall be shown in tabular form on the diagram or in the report.

## 2.20.5 Coordination Study

The study shall demonstrate that the maximum possible degree of selectivity has been obtained between devices specified, consistent with protection of equipment and conductors from damage from overloads and fault conditions. The study shall include a description of the coordination of the protective devices in this project. Provide a written narrative that describes: which devices may operate in the event of a fault at each bus; the logic used to arrive at device ratings and settings; situation where system coordination is not achievable due to device limitations (an analysis of any device curves which order overlap); coordination between upstream and downstream devices; and relay settings. Recommendations to improve or enhance system reliability, and detail where such changes would involve additions or modifications to the contract and cost changes (addition or reduction) shall be provided. Composite coordination plots shall be provided on log-log graph paper.

## 2.20.6 Study Report

- a. The report shall include a narrative: the analyses performed; the bases and methods used; and the desired method of coordinated protection of the power system.
- b. The study shall include descriptive and technical data for existing devices and new protective devices proposed. The data shall include manufacturers published data, nameplate data, and definition of the fixed or adjustable features of the existing or new protective devices.
- c. The report shall document utility company data including system voltages, fault MVA, system X/R ratio, time-current characteristic curves, current transformer ratios, and relay device curves and protective device ratings and settings.
- d. The report shall contain fully coordinated composite time-current characteristic curves for each bus in the system, as required to ensure coordinated power system protection between protective devices or equipment. The report shall include recommended ratings and settings of all protective devices in tabulated form.
- e. The report shall provide the calculations performed for the analyses, including computer analysis programs utilized. The name of the software package, developer, and version number shall be provided.

### PART 3 EXECUTION

### 3.1 GROUNDING

Grounding shall be in conformance with NFPA 70, the contract drawings, and the following specifications.

### 3.1.1 Ground Rods

The resistance to ground shall be measured using the fall-of-potential method described in IEEE Std 81. The maximum resistance of a driven ground shall not exceed 25 ohms under normally dry conditions. If this resistance cannot be obtained with a single rod, 2 additional rods not less than 10 feet on centers, or if sectional type rods are used, 2 additional sections may be coupled and driven with the first rod. In high-ground-resistance, UL listed chemically charged ground rods may be used. If the resultant resistance exceeds 25 ohms measured not less than 48 hours after rainfall, the Contracting Officer shall be notified immediately. Connections below grade shall be fusion welded. Connections above grade shall be fusion welded or shall use UL 467 approved connectors.

## 3.1.2 Grounding Conductors

A green equipment grounding conductor, sized in accordance with NFPA 70 shall be provided, regardless of the type of conduit. Equipment grounding bars shall be provided in all panelboards. The equipment grounding conductor shall be carried back to the service entrance grounding connection or separately derived grounding connection. All equipment grounding conductors, including metallic raceway systems used as such, shall be bonded or joined together in each wiring box or equipment enclosure. Metallic raceways and grounding conductors shall be checked to assure that they are wired or bonded into a common junction. Metallic boxes and enclosures, if used, shall also be bonded to these grounding conductors by an approved means per NFPA 70. When switches, or other utilization devices are installed, any designated grounding terminal on these devices shall also be bonded to the equipment grounding conductor junction with a short jumper.

## 3.2 WIRING METHODS

Wiring shall conform to NFPA 70, the contract drawings, and the following specifications. Unless otherwise indicated, wiring shall consist of insulated conductors installed in rigid zinc-coated steel conduit, electrical metallic tubing, or intermediate metal conduit. Wire fill in conduits shall be based on NFPA 70 for the type of conduit and wire insulations specified. Wire fill in conduits located in Class I or II hazardous areas shall be limited to 25 percent of the cross sectional area of the conduit.

## 3.2.1 Conduit and Tubing Systems

Conduit and tubing systems shall be installed as indicated. Conduit sizes shown are based on use of copper conductors with insulation types as described in paragraph WIRING METHODS. Minimum size of raceways shall be 1/2 inch. Only metal conduits will be permitted when conduits are required for shielding or other special purposes indicated, or when required by conformance to NFPA 70. Electrical metallic tubing (EMT) may be installed only within buildings. EMT may be installed in concrete and grout in dry locations. EMT installed in concrete or grout shall be provided with concrete tight fittings. EMT shall not be installed in damp or wet locations, or the air space of exterior masonry cavity walls. Bushings, manufactured fittings or boxes providing equivalent means of protection shall be installed on the ends of all conduits and shall be of the insulating type, where required by NFPA 70. Only UL listed adapters shall be used to connect EMT to rigid metal conduit, cast boxes, and conduit

bodies. Except as otherwise specified, IMC may be used as an option for rigid steel conduit in areas as permitted by NFPA 70. Raceways shall not be installed under the firepits of boilers and furnaces and shall be kept 6 inches away from parallel runs of flues, steam pipes and hot-water pipes. Raceways shall be concealed within finished walls, ceilings, and floors unless otherwise shown. Raceways crossing structural expansion joints or seismic joints shall be provided with suitable expansion fittings or other suitable means to compensate for the building expansion and contraction and to provide for continuity of grounding.

### 3.2.1.1 Pull Wires

A pull wire shall be inserted in each empty raceway in which wiring is to be installed if the raceway is more than 50 feet in length and contains more than the equivalent of two 90-degree bends, or where the raceway is more than 150 feet in length. The pull wire shall be of No. 14 AWG zinc-coated steel, or of plastic having not less than 200 pounds per square inch tensile strength. Not less than 10 inches of slack shall be left at each end of the pull wire.

## 3.2.1.2 Conduit Stub-Ups

Where conduits are to be stubbed up through concrete floors, a short elbow shall be installed below grade to transition from the horizontal run of conduit to a vertical run. Wiring shall be extended in rigid threaded conduit to equipment, except that where required, flexible conduit may be used 6 inches above the floor.

## 3.2.1.3 Below Slab-on-Grade or in the Ground

Electrical wiring below slab-on-grade shall be protected by a conduit system. Conduit passing vertically through slabs-on-grade shall be PVC-coated rigid steel or IMC. Rigid steel or IMC conduits installed below slab-on-grade or in the earth shall have a factory-applied polyvinyl chloride, plastic resin, or epoxy coating system.

## 3.2.1.4 Changes in Direction of Runs

Changes in direction of runs shall be made with symmetrical bends or cast-metal fittings. Field-made bends and offsets shall be made with an approved hickey or conduit-bending machine. Crushed or deformed raceways shall not be installed. Trapped raceways in damp and wet locations shall be avoided where possible. Lodgment of plaster, dirt, or trash in raceways, boxes, fittings and equipment shall be prevented during the course of construction. Clogged raceways shall be cleared of obstructions or shall be replaced.

### 3.2.1.5 Supports

Metallic conduits and tubing, and the support system to which they are attached, shall be securely and rigidly fastened in place to prevent vertical and horizontal movement at intervals of not more than 10 feet and within 3 feet of boxes, cabinets, and fittings, with approved pipe straps, wall brackets, conduit clamps, conduit hangers, threaded C-clamps, beam clamps, or ceiling trapeze. Loads and supports shall be coordinated with supporting structure to prevent damage or deformation to the structure. Loads shall not be applied to joist bridging. Attachment shall be by toggle bolts on hollow masonry units; by expansion bolts on concrete or brick; by machine screws, welded threaded studs, heat-treated or

spring-steel-tension clamps on steel work. Nail-type nylon anchors or threaded studs driven in by a powder charge and provided with lock washers and nuts may be used in lieu of expansion bolts or machine screws. Raceways or pipe straps shall not be welded to steel structures. In partitions of light steel construction, sheet-metal screws may be used. Raceways shall not be supported using wire or nylon ties. Raceways shall be independently supported from the structure. Upper raceways shall not be used as a means of support for lower raceways. Supporting means shall not be shared between electrical raceways and mechanical piping or ducts. Cables and raceways shall not be supported by ceiling grids. Except where permitted by NFPA 70, wiring shall not be supported by ceiling support systems. Conduits shall be fastened to sheet-metal boxes and cabinets with two locknuts where required by NFPA 70, where insulating bushings are used, and where bushings cannot be brought into firm contact with the box; otherwise, a single locknut and bushing may be used. Threadless fittings for electrical metallic tubing shall be of a type approved for the conditions encountered. Additional support for horizontal runs is not required when EMT rests on steel stud cutouts.

## 3.2.1.6 Exposed Raceways

Exposed raceways shall be installed parallel or perpendicular to walls, structural members, or intersections of vertical planes and ceilings. Raceways above accessible ceilings shall be considered as exposed installations in accordance with NFPA 70 definitions.

## 3.2.1.7 Communications Raceways

Communications raceways indicated shall be installed in accordance with the previous requirements for conduit and tubing and with the additional requirement that no length of run shall exceed 50 feet for 1/2 inch and 3/4 inch sizes, and 100 feet for 1 inch or larger sizes, and shall not contain more than two 90-degree bends or the equivalent. Additional pull or junction boxes shall be installed to comply with these limitations whether or not indicated. Inside radii of bends in conduits of 1 inch size or larger shall not be less than ten times the nominal diameter.

### 3.2.2 Cables and Conductors

Installation shall conform to the requirements of NFPA 70.

## 3.2.2.1 Sizing

Unless otherwise noted, all sizes are based on copper conductors and the insulation types indicated. Sizes shall be not less than indicated. Branch-circuit conductors shall be not smaller than No. 12 AWG. Conductors for branch circuits of 120 volts more than 100 feet long and of 277 volts more than 230 feet long, from panel to load, shall be no smaller than No. 10 AWG. Class 1 remote control and signal circuit conductors shall be not less than No. 14 AWG. Class 2 remote control and signal circuit conductors shall be not less than No. 16 AWG. Class 3 low-energy, remote-control and signal circuits shall be not less than No. 22 AWG.

### 3.2.2.2 Use of Aluminum Conductors in Lieu of Copper

Aluminum conductors shall not be used.

## 3.2.2.3 Conductor Splicing

Splices shall be made in an accessible location.

a. Copper Conductors, 600 Volt and Under: Splices in conductors No. 10 AWG and smaller diameter shall be made with an insulated, pressure-type connector. Splices in conductors No. 8 AWG and larger diameter shall be made with a solderless connector and insulated with tape or heat-shrink type insulating material equivalent to the conductor insulation.

## 3.2.2.4 Conductor Identification and Tagging

Power, control, and signal circuit conductor identification shall be provided within each enclosure where a tap, splice, or termination is made. Where several feeders pass through a common pull box, the feeders shall be tagged to indicate clearly the electrical characteristics, circuit number, and panel designation. Phase conductors of low voltage power circuits shall be identified by color coding. Phase identification by a particular color shall be maintained continuously for the length of a circuit, including junctions.

a. Color coding shall be provided for service, feeder, branch, and ground conductors. Color shall be green for grounding conductors and white for neutrals; except where neutrals of more than one system are installed in the same raceway or box, other neutral shall be white with colored (not green) stripe. The color coding for 3-phase and single-phase low voltage systems shall be as follows:

120/208-volt, 3-phase: Black(A), red(B), and blue(C). 277/480-volt, 3-phase: Brown(A), orange(B), and yellow(C).

- b. Conductor phase and voltage identification shall be made by color-coded insulation for all conductors smaller than No. 6 AWG. For conductors No. 6 AWG and larger, identification shall be made by color-coded insulation, or conductors with black insulation may be furnished and identified by the use of half-lapped bands of colored electrical tape wrapped around the insulation for a minimum of 3 inches of length near the end, or other method as submitted by the Contractor and approved by the Contracting Officer.
- c. Control and signal circuit conductor identification shall be made by color-coded insulated conductors, plastic-coated self-sticking printed markers, permanently attached stamped metal foil markers, or equivalent means as approved. Control circuit terminals of equipment shall be properly identified. Terminal and conductor identification shall match that shown on approved detail drawings. Hand lettering or marking is not acceptable.

## 3.3 BOXES AND SUPPORTS

Boxes shall be provided in the wiring or raceway systems where required by NFPA 70 for pulling of wires, making connections, and mounting of devices or fixtures. Pull boxes shall be furnished with screw-fastened covers. Indicated elevations are approximate, except where minimum mounting heights for hazardous areas are required by NFPA 70. Unless otherwise indicated, boxes for wall switches shall be mounted 48 inches above finished floors.

## 3.3.1 Box Applications

Each box shall have not less than the volume required by NFPA 70 for number of conductors enclosed in box. Boxes for metallic raceways shall be listed for the intended use when located in normally wet locations, when flush or surface mounted on outside of exterior surfaces, or when located in hazardous areas. Boxes installed in wet locations and boxes installed flush with the outside of exterior surfaces shall be gasketed. Boxes for mounting lighting fixtures shall be not less than 4 inches square, or octagonal, except smaller boxes may be installed as required by fixture configuration, as approved. Cast-metal boxes with 3/32 inch wall thickness are acceptable. Large size boxes shall be NEMA 1, 3R, 7, or as shown. Boxes for use in masonry-block or tile walls shall be square-cornered, tile-type, or standard boxes having square-cornered, tile-type covers.

### 3.3.2 Brackets and Fasteners

Boxes and supports shall be fastened with bolts and metal expansion shields on concrete or brick, with toggle bolts on hollow masonry units, and with machine screw or welded studs on steel work. Threaded studs driven in by powder charge and provided with lockwashers and nuts, or nail-type nylon anchors may be used in lieu of expansion shields, or machine screws. The use of brackets which depend on gypsum wallboard or plasterboard for primary support will not be permitted. In partitions of light steel construction, bar hangers with 1 inch long studs, mounted between metal wall studs or metal box mounting brackets shall be used to secure boxes to the building structure. When metal box mounting brackets are used, additional box support shall be provided on the side of the box opposite the brackets. This additional box support shall consist of a minimum 12 inch long section of wall stud, bracketed to the opposite side of the box and secured by two screws through the wallboard on each side of the stud. Metal screws may be used in lieu of the metal box mounting brackets.

## 3.3.3 Mounting in Walls, Ceilings, or Recessed Locations

In walls or ceilings of concrete, tile, or other non-combustible material, boxes shall be installed so that the edge of the box is not recessed more than 1/4 inch from the finished surface. Boxes mounted in combustible walls or ceiling material shall be mounted flush with the finished surface. The use of gypsum or plasterboard as a means of supporting boxes will not be permitted. Boxes installed for concealed wiring shall be provided with suitable extension rings or plaster covers, as required. The bottom of boxes installed in masonry-block walls for concealed wiring shall be mounted flush with the top of a block to minimize cutting of the blocks, and boxes shall be located horizontally to avoid cutting webs of block. Separate boxes shall be provided for flush or recessed fixtures when required by the fixture terminal operating temperature, and fixtures shall be readily removable for access to the boxes unless ceiling access panels are provided.

## 3.3.4 Installation in Overhead Spaces

In open overhead spaces, cast-metal boxes threaded to raceways need not be separately supported except where used for fixture support; cast-metal boxes having threadless connectors and sheet metal boxes shall be supported directly from the building structure or by bar hangers. Hangers shall not be fastened to or supported from joist bridging. Where bar hangers are used, the bar shall be attached to raceways on opposite sides of the box and the raceway shall be supported with an approved type fastener not more than 24 inches from the box.

### 3.4 DEVICE PLATES

One-piece type device plates shall be provided for all outlets and fittings. Plates shall be of satin finish corrosion resistant steel. Screws shall be of metal with countersunk heads, in a color to match the finish of the plate. Plates shall be installed with all four edges in continuous contact with finished wall surfaces without the use of mats or similar devices. Plaster fillings will not be permitted. Plates shall be installed with an alignment tolerance of 1/16 inch. The use of sectional-type device plates will not be permitted. Plates installed in wet locations shall be gasketed and provided with a hinged, gasketed cover, unless otherwise specified.

# 3.5 RECEPTACLES

## 3.5.1 Duplex, 15-ampere, 125 volt

Duplex receptacles shall be rated 15 amperes, 125 volts, two-pole, three-wire, grounding type with polarized parallel slots. Bodies shall be of gray to match color of switch handles in the same room or to harmonize with the color of the respective wall, and supported by mounting strap having plaster ears. Contact arrangement shall be such that contact is made on two sides of an inserted blade. Receptacle shall be side- or back-wired with two screws per terminal. The third grounding pole shall be connected to the metal mounting yoke. Receptacles with ground fault circuit interrupters shall have the current rating as indicated, and shall be UL Class A type unless otherwise shown. Ground fault circuit protection shall be provided as required by NFPA 70 and as indicated on the drawings.

## 3.5.2 Weatherproof Applications

Weatherproof receptacles shall be suitable for the environment, wet as applicable, and the housings shall be labeled to identify the allowable use. Receptacles shall be marked in accordance with UL 514A for the type of use indicated; "Wet Locations". Assemblies shall be installed in accordance with the manufacturer's recommendations.

## 3.5.2.1 Wet Locations

Receptacles in wet locations shall be installed in an assembly rated for such use whether the plug is inserted or withdrawn, unless otherwise indicated. In a duplex installation, the receptacle cover shall be configured to shield the connections whether one or both receptacles are in use.

### 3.6 WALL SWITCHES

Wall switches shall be of the totally enclosed tumbler type. The wall switch handle and switch plate color shall be gray. Wiring terminals shall be of the screw type or of the solderless pressure type having suitable conductor-release arrangement. Not more than one switch shall be installed in a single-gang position. Switches shall be rated 15-ampere 277-volt for use on alternating current only.

### 3.7 FUSES

Equipment provided under this contract shall be provided with a complete set of properly rated fuses when the equipment manufacturer utilize fuses

in the manufacture of the equipment, or if current-limiting fuses are required to be installed to limit the ampere-interrupting capacity of circuit breakers or equipment to less than the maximum available fault current at the location of the equipment to be installed. Fuses shall have a voltage rating of not less than the phase-to-phase circuit voltage, and shall have the time-current characteristics required for effective power system coordination. Time-delay and non-time-delay options shall be as specified.

## 3.7.1 Cartridge Fuses; Current-Limiting Type

Cartridge fuses, current-limiting type, Class RK1 shall have tested interrupting capacity not less than 100,000 amperes. Fuse holders shall be the type that will reject all Class H fuses.

## 3.7.2 Motor and Transformer Circuit Fuses

Motor, motor controller, transformer, and inductive circuit fuses shall be Class RK1 or RK5, current-limiting, time-delay with 200,000 amperes interrupting capacity.

### 3.8 MOTORS

Each motor shall conform to the hp and voltage ratings indicated, and shall have a service factor and other characteristics that are essential to the proper application and performance of the motors under conditions shown or specified. Unless otherwise specified, all motors shall have open frames, and continuous-duty classification based on a 40 degree C ambient temperature reference. Polyphase motors shall be squirrel-cage type, having normal-starting-torque and low-starting-current characteristics, unless other characteristics are specified in other sections of these specifications or shown on contract drawings. The Contractor shall be responsible for selecting the actual horsepower ratings and other motor requirements necessary for the applications indicated. When electrically driven equipment furnished under other sections of these specifications materially differs from the design, the Contractor shall make the necessary adjustments to the wiring, disconnect devices and branch-circuit protection to accommodate the equipment actually installed.

## 3.9 MOTOR CONTROL

Each motor or group of motors requiring a single control shall be provided under other sections of these specifications with a suitable controller and devices that will perform the functions as specified for the respective motors. Each motor of 1/8 hp or larger shall be provided with thermal-overload protection. Polyphase motors shall have overload protection in each ungrounded conductor. The overload-protection device shall be provided either integral with the motor or controller. Unless otherwise specified, the protective device shall be of the manually reset type.

## 3.9.1 Reduced-Voltage Starters

Reduced-voltage starters shall be provided for polyphase motors 20 hp or larger.

## 3.9.2 Motor Control Centers

Control centers shall be indoor type and shall contain combination starters

and other equipment as indicated. Each control center shall be mounted on floor sills or mounting channels. Each circuit shall have a suitable laminated plastic nameplate with white cut letters. Combination starters shall be provided with circuit breakers. Motor control centers shall be provided with a full-length ground bus bar.

### 3.9.3 Contacts

Unless otherwise indicated, contacts in miscellaneous control devices such as float switches, pressure switches, and auxiliary relays shall have current and voltage ratings in accordance with NEMA ICS 2 for rating designation B300.

### 3.10 MOTOR-DISCONNECT MEANS

Each motor shall be provided with a disconnecting means when required by NFPA 70 even though not indicated. Switches shall disconnect all ungrounded conductors.

## 3.11 LIGHTING FIXTURES, LAMPS AND BALLASTS

This paragraph shall cover the installation of lamps, lighting fixtures and ballasts in interior or building mounted applications.

## 3.11.1 Lamps

Lamps of the type, wattage, and voltage rating indicated shall be delivered to the project in the original cartons and installed just prior to project completion. Lamps installed and used for working light during construction shall be replaced prior to turnover to the Government if more than 15% of their rated life has been used. Lamps shall be tested for proper operation prior to turn-over and shall be replaced if necessary with new lamps from the original manufacturer. 10% spare lamps of each type, from the original manufacturer, shall be provided.

## 3.11.2 Lighting Fixtures

Fixtures shall be as shown and shall conform to the following specifications and shall be as detailed on the drawings. Illustrations shown on the drawings are indicative of the general type desired and are not intended to restrict selection to fixtures of any particular manufacturer. Fixtures of similar designs and equivalent energy efficiency, light distribution and brightness characteristics, and of equal finish and quality will be acceptable if approved. In suspended acoustical ceilings with fluorescent fixtures, the fluorescent emergency light fixtures shall be furnished with self-contained battery packs.

### 3.11.2.1 Accessories

Accessories such as straps, mounting plates, nipples, or brackets shall be provided for proper installation.

## 3.11.2.2 Ceiling Fixtures

Ceiling fixtures shall be coordinated with and suitable for installation in, on or from the ceiling as shown. Installation and support of fixtures shall be in accordance with NFPA 70 and manufacturer's recommendations. Where seismic requirements are specified herein, fixtures shall be supported as shown or specified. Surface-mounted fixtures shall be

suitable for fastening to the ceiling panel structural supports. Fixtures in continuous rows shall have internal wireway systems for end to end wiring and shall be properly aligned to provide a straight and continuous row without bends, gaps, light leaks or filler pieces.

## 3.11.2.3 Fixtures for Installation in Grid Type Ceilings

Work above the ceiling shall be coordinated among the trades to provide the lighting layout shown. Fixtures in continuous rows shall be coordinated between trades prior to ordering. Fixtures shall be mounted using independent supports capable of supporting the entire weight of the fixture. No fixture shall rest solely on the ceiling grid. Recessed fixtures installed in seismic areas should be installed utilizing specially designed seismic clips. Junction boxes shall be supported at four points.

## 3.11.2.4 Suspended Fixtures

Suspended fixtures shall be provided with swivel hangers or hand-straights so that they hang plumb. Pendants, rods, or chains 4 feet or longer excluding fixture shall be braced to prevent swaying using three cables at 120 degrees of separation. Steel fixtures shall be supported to prevent "oil-canning" effects. Fixture finishes shall be free of scratches, nicks, dents, and warps, and shall match the color and gloss specified. Pendants shall be finished to match fixtures.

Suspended fixtures installed in seismic areas shall have 45% swivel hangers and shall be located with no obstructions within the 45% range in all directions. The stem, canopy and fixture shall be capable of 45% swing.

### 3.12 EQUIPMENT CONNECTIONS

Wiring not furnished and installed under other sections of the specifications for the connection of electrical equipment as indicated on the drawings shall be furnished and installed under this section of the specifications. Connections shall comply with the applicable requirements of paragraph WIRING METHODS. Flexible conduits 6 feet or less in length shall be provided to all electrical equipment subject to periodic removal, vibration, or movement and for all motors. All motors shall be provided with separate grounding conductors. Liquid-tight conduits shall be used in damp or wet locations.

## 3.12.1 Motors and Motor Control

Motors, motor controls, and motor control centers shall be installed in accordance with NFPA 70, the manufacturer's recommendations, and as indicated. Wiring shall be extended to motors, motor controls, and motor control centers and terminated.

### 3.13 CIRCUIT PROTECTIVE DEVICES

The Contractor shall calibrate, adjust, set and test each new adjustable circuit protective device to ensure that they will function properly prior to the initial energization of the new power system under actual operating conditions.

## 3.14 PAINTING AND FINISHING

Field-applied paint on exposed surfaces shall be provided under Section 09900 PAINTS AND COATINGS.

### 3.15 REPAIR OF EXISTING WORK

The work shall be carefully laid out in advance, and where cutting, channeling, chasing, or drilling of floors, walls, partitions, ceiling, or other surfaces is necessary for the proper installation, support, or anchorage of the conduit, raceways, or other electrical work, this work shall be carefully done, and any damage to building, piping, or equipment shall be repaired by skilled mechanics of the trades involved at no additional cost to the Government.

### 3.16 FIELD TESTING

Field testing shall be performed in the presence of the Contracting Officer. The Contractor shall notify the Contracting Officer 20 days prior to conducting tests. The Contractor shall furnish all materials, labor, and equipment necessary to conduct field tests. The Contractor shall perform all tests and inspection recommended by the manufacturer unless specifically waived by the Contracting Officer. The Contractor shall maintain a written record of all tests which includes date, test performed, personnel involved, devices tested, serial number and name of test equipment, and test results. All field test reports will be signed and dated by the Contractor.

## 3.16.1 Safety

The Contractor shall provide and use safety devices such as rubber gloves, protective barriers, and danger signs to protect and warn personnel in the test vicinity. The Contractor shall replace any devices or equipment which are damaged due to improper test procedures or handling.

### 3.16.2 Ground-Resistance Tests

The resistance of each grounding electrode and each grounding electrode system shall be measured using the fall-of-potential method defined in IEEE Std 81. Soil resistivity in the area of the grid shall be measured concurrently with the grid measurements. Ground resistance measurements shall be made before the electrical distribution system is energized and shall be made in normally dry conditions not less than 48 hours after the last rainfall. Resistance measurements of separate grounding electrode systems shall be made before the systems are bonded together below grade. The combined resistance of separate systems may be used to meet the required resistance, but the specified number of electrodes must still be provided.

- a. Single rod electrode 25 ohms.
- b. Electrode System 25 ohms.

## 3.16.3 Ground-Grid Connection Inspection

All below-grade ground-grid connections will be visually inspected by the Contracting Officer before backfilling. The Contractor shall notify the Contracting Officer 48 hours before the site is ready for inspection.

## 3.16.4 Cable Tests

The Contractor shall be responsible for identifying all equipment and devices that could be damaged by application of the test voltage and

ensuring that they have been properly disconnected prior to performing insulation resistance testing. An insulation resistance test shall be performed on all low voltage cables after the cables are installed in their final configuration and prior to energization. The test voltage shall be 500 volts DC applied for one minute between each conductor and ground and between all possible combinations of conductors. The minimum value of resistance shall be:

R in megohms = (rated voltage in kV + 1) x 1000/(length of cable in feet)

Each cable failing this test shall be repaired or replaced. The repaired cable system shall then be retested until failures have been eliminated.

## 3.16.4.1 Low Voltage Cable Tests

- a. Continuity test.
- b. Insulation resistance test.

## 3.16.5 Motor Tests

- a. Phase rotation test to ensure proper directions.
- b. Operation and sequence of reduced voltage starters.
- c. High potential test on each winding to ground.
- d. Insulation resistance of each winding to ground.
- e. Vibration test.
- f. Dielectric absorption test on motor and starter.

### 3.16.6 Circuit Breaker Tests

The following field tests shall be performed on circuit breakers.

## 3.16.6.1 Circuit Breakers, Molded Case

- a. Insulation resistance test phase-to-phase, all combinations.
- b. Insulation resistance test phase-to-ground, each phase.
- c. Closed breaker contact resistance test.
- d. Manual operation of the breaker.

# 3.16.7 Motor Control Centers

- a. Insulation resistance test phase-to-phase, all combinations.
- b. Insulation resistance test phase-to-ground, each phase.
- c. Manual and electrical operational tests.

### 3.17 OPERATING TESTS

After the installation is completed, and at such time as the Contracting Officer may direct, the Contractor shall conduct operating tests for

approval. The equipment shall be demonstrated to operate in accordance with the specified requirements. An operating test report shall be submitted in accordance with paragraph FIELD TEST REPORTS.

## 3.18 FIELD SERVICE

# 3.18.1 Onsite Training

The Contractor shall conduct a training course for the operating staff as designated by the Contracting Officer. The training period shall consist of a total of 16 hours of normal working time and shall start after the system is functionally completed but prior to final acceptance tests. The course instruction shall cover pertinent points involved in operating, starting, stopping, servicing the equipment, as well as all major elements of the operation and maintenance manuals. Additionally, the course instructions shall demonstrate all routine maintenance operations.

### 3.19 ACCEPTANCE

Final acceptance of the facility will not be given until the Contractor has successfully completed all tests and after all defects in installation, material or operation have been corrected.

-- End of Section --

